

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL		5. MINERAL LEASE NO: ML 3355	6. SURFACE: State
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		8. UNIT or CA AGREEMENT NAME: CHAPITA WELLS UNIT	
2. NAME OF OPERATOR: EOG RESOURCES, INC.		9. WELL NAME and NUMBER: CHAPITA WELLS UNIT 722-32	
3. ADDRESS OF OPERATOR: P.O. BOX 1815 CITY VERNAL STATE UT ZIP 84078		PHONE NUMBER: (435) 789-0790	
10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 9S 23E S	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2071 FSL 713 FEL 39.990914 LAT 109.343875/LON AT PROPOSED PRODUCING ZONE: SAME		12. COUNTY: UINTAH	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 54.4 MILES SOUTH OF VERNAL, UT		13. STATE: UTAH	
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 713	16. NUMBER OF ACRES IN LEASE: 640	17. NUMBER OF ACRES ASSIGNED TO THIS WELL:	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 36	19. PROPOSED DEPTH: 6,500	20. BOND DESCRIPTION: NM 2308	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5202 GL	22. APPROXIMATE DATE WORK WILL START:	23. ESTIMATED DURATION: 45 DAYS	

24.

PROPOSED CASING AND CEMENTING PROGRAM					
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
17-1/2	13-3/8	H-40	48#	0-45	SEE ATTACHED EIGHT POINT PLAN
12-1/4	9-5/8	J-55	36#	45-2300	SEE ATTACHED EIGHT POINT PLAN
7-7/8	4-1/2	N-80	11.6#	2300-TD	SEE ATTACHED EIGHT POINT PLAN

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) Kaylene R. Gardner TITLE Sr. Regulatory Assistant

SIGNATURE [Signature] DATE 11/10/2006

(This space for State use only)

API NUMBER ASSIGNED: 43-047-38862

(11/2001)

Approved by the
Utah Division of
Oil, Gas and Mining

APPROVAL: [Signature]

Date: 01-18-07

By: [Signature]

RECEIVED
NOV 14 2006

DIV. OF OIL, GAS & MINING

T9S, R23E, S.L.B.&M.

EOG RESOURCES, INC.


Well location, CWU #722-32, located as shown in the NE 1/4 SE 1/4 of Section 32, T9S, R23E, S.L.B.&M., Uintah County, Utah.

BASIS OF ELEVATION

BENCHMARK 58 EAM (1965) LOCATED IN THE NE 1/4 OF SECTION 30, T9S, R23E, S.L.B.&M. TAKEN FROM THE RED WASH SE, QUADRANGLE, UTAH, UTAH COUNTY 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5132 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.




CERTIFICATION

THIS IS TO CERTIFY THAT THE ABOVE WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEY MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

ROBERT L. [Signature]
REGISTERED LAND SURVEYOR
REGISTRATION NO. 10738
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 10-25-06	DATE DRAWN: 10-27-06
PARTY G.S. K.C. S.L.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE EOG RESOURCES, INC.	



(NAD 83)
LATITUDE = 39°59'27.29" (39.990914)
LONGITUDE = 109°20'37.95" (109.343875)
(NAD 27)
LATITUDE = 39°59'27.41" (39.990947)
LONGITUDE = 109°20'35.51" (109.343197)

LEGEND:

- └─ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

EIGHT POINT PLAN

CHAPITA WELLS UNIT 722-32 NE/SE, SEC. 32, T9S, R23E, S.L.B.&M. UINTAH COUNTY, UTAH

1. & 2 ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	DEPTH (KB)
Green River FM	1,355'
Wasatch	4,289'
Chapita Wells	4,824'
Buck Canyon	5,510'
North Horn	6,109'
Island	6,331'

EST. TD: 6,500' or 200' ± below Island Top

Anticipated BHP: 3,210 Psig

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

3. PRESSURE CONTROL EQUIPMENT:

Production Hole – 5000 Psig
BOP schematic diagrams attached.

4. CASING PROGRAM:

	<u>HOLE SIZE</u>	<u>INTERVAL</u>	<u>SIZE</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>THREAD</u>	<u>RATING FACTOR</u>		
							<u>COLLAPSE</u>	<u>BURST</u>	<u>TENSILE</u>
Conductor:	17 ½"	0' – 45'	13 ¾"	48.0#	H-40	STC	770 PSI	1730 PSI	322,000#
Surface	12-1/4"	45' – 2,300'KB±	9-5/8"	36.0#	J-55	STC	2020 PSI	3520 Psi	394,000#
Production:	7-7/8"	2,300'± – TD	4-½"	11.6#	N-80	LTC	6350 PSI	7780 Psi	223,000#

Note: 12-¼" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-5/8" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone. All casing will be new or inspected.

5. Float Equipment:

Surface Hole Procedure (0' - 2300'±)

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

EIGHT POINT PLAN
CHAPITA WELLS UNIT 722-32
NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

Float Equipment: (Cont'd)

Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-½", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. (30± total). Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (Surface - 2300'±):

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD): Anticipated mud weight 9.0 – 9.5 ppg depending on actual wellbore conditions encountered while drilling.

2300'± - TD A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

7. VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 2 – Item E: Special Drilling Operations

EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. Due to reduce location excavation, the blooie line will be approximately 75' in length

8. EVALUATION PROGRAM:

Logs: Mud log from base of surface casing to TD.

Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following:
Cement Bond / Casing Collar Locator and Pulsed Neutron

EIGHT POINT PLAN
CHAPITA WELLS UNIT 722-32
NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

9. CEMENT PROGRAM:

Surface Hole Procedure (Surface - 2300'±):

Lead: Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.

Tail: Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Top Out: As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Note: Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

Production Hole Procedure (2300'± - TD)

Lead: **110 sks:** 35:65 Poz "G" w/4% D20 (Bentonite), 2% D174 (Extender), 0.2% D65 (Dispersant), 0.2% D46 (Antifoam), 0.75% D112 (Fluid Loss Additive), 0.200% D13 (Retarder), 0.25 pps D29 (cello flakes) mixed at 13.0 ppg, 1.75 ft³/sk., 9.19 gps water.

Tail: **480 sks:** 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9 gps water.

Note: The above number of sacks is based on gauge-hole calculation.
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.
Final Cement volumes will be based upon gauge-hole plus 45% excess.

10. ABNORMAL CONDITIONS:

Surface Hole (Surface - 2300'±):

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

EIGHT POINT PLAN

CHAPITA WELLS UNIT 722-32
NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring


12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

(Attachment: BOP Schematic Diagram)


**EOG RESOURCES 11" 5,000 PSI W.P. BOP
CONFIGURATION**

PAGE 1 OF 2



EOG RESOURCES CHOKE MANIFOLD CONFIGURATION W/ 5,000 PSI WP VALVES

PAGE 2 OF



Testing Procedure:

1. BOP will be tested with a professional tester to conform to Onshore Order #2.
2. Blind and Pipe rams will be tested to rated working pressure, 5,000 psi.
3. Annular Preventer will be tested to 50% working pressure, 2,500 psi.
Casing will be tested to 0.22 psi / ft. or 1,500 psi. Not to exceed 70% of burst strength, **whichever is greater.**
4. All lines subject to well pressure will be tested to the same pressure as blind and pipe rams.
5. All BOPE specifications and configurations will meet Onshore Order #2 requirements.



**CHAPITA WELLS UNIT 722-32
NE/SE, Section 32, T9S, R23E
Uintah County, Utah**

SURFACE USE PLAN

NOTIFICATION REQUIREMENTS

- | | |
|----------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------|
| Location Construction: | Forty-eight (48) hours prior to construction of location and access roads. |
| Location Completion: | Prior to moving on the drilling rig. |
| Spud Notice: | At least twenty-four (24) hours prior to spudding the well. |
| Casing String and Cementing: | Twenty-four (24) hours prior to running casing and cementing all casing strings. |
| BOP and related Equipment Tests: | Twenty-four (24) hours prior to running casing and tests. |
| First Production Notice: | Within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days. |

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

The well pad is approximately 325 feet long with a 246-foot width, containing 1.84 acres more or less. New surface disturbance associated with the well pad is estimated to be approximately 1.84 acres.

1. EXISTING ROADS:

- A. See attached Wellsite Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing roads.
- B. The proposed well site is located approximately 55.0 miles south of Vernal, Utah – See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary.

2. PLANNED ACCESS ROAD:

No new access road will be required. The existing access road for Chapita Wells Unit 852-32 will be utilized to access the proposed location.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation or debris in the drainage crossings nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by run off water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

As operator, EOG Resources, Inc. shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

Traveling off the 30 foot right-of-way will not be allowed. The access road and associated drainage structures will be constructed and maintained in accordance with road guidelines contained in the joint BLM/USFS publication: Surface Operating Standards for Oil and Gas Exploration and Development, Third Edition, and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction. During the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and drainage ditches and culverts will be kept clear and free flowing.

3. LOCATION OF EXISTING WELLS WITHIN A ONE-MILE RADIUS:

See attached TOPO map "C" for the location of wells within a one-mile radius.

4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

A. On Well Pad

1. Production facilities will be set on location if the well is successfully completed for production. Facilities will consist of wellhead valves, combo separator-dehy unit with meter, two (2) 400 BBL vertical tanks and attaching piping.
2. Gas gathering lines – A 4" gathering line will be buried from dehy to the edge of the location.

B. Off Well Pad

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire contents of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. **All existing facilities will be painted with Carlsbad Canyon.** Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

5. LOCATION AND TYPE OF WATER SUPPLY:

- A. Water supply will be from Ouray Municipal Water Plant at Ouray, Utah, and/ or Target Trucking Inc.'s water source in the SW/SW. Sec 35, T9S, R22E Uintah County, Utah (State Water Right # 49-1501, and/or Bonanza Power Plant water source in Sec 26, T8S, R23E Uintah County, UT (State Water Right # 49-225(A31368)). Water will be hauled by a licensed trucking company.
- B. Water will be hauled by a licensed trucking company.
- C. No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIALS:

- A. All construction material for this location and access road will be of native borrow and soil accumulated during the construction of the location.
- B. No mineral materials will be required.

7. METHODS OF HANDLING WASTE DISPOSAL:

A. METHODS AND LOCATION

1. Cuttings will be confined in the reserve pit.
 2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
 3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at the Uintah County Landfill.
 4. Produced wastewater will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. After the 90 day period, the produced water will be contained in a tank on location and then disposed of at one of the following three locations: Natural Buttes Unit 21-20B SWD, Ace Disposal, or EOG Resources, Inc. drilling operations (Chapita Wells Unit, Natural Buttes Unit & Stagecoach Unit).
 5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on the drilling rig to avoid leakage of oil to the pit.
- B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in the reserve pit or by removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to the reserve pit will be avoided by flaring them off in the flare pit at the time of recovery.

The reserve pit will be constructed so as not to leak, break, or allow discharge. If the reserve pit requires padding prior to lining (due to rocky conditions) felt padding will be used.

The reserve pit shall be lined with felt and a 16 millimeter plastic liner.

EOG Resources, Inc. maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances which are used during the course of construction, drilling, completion, and production operations for this project. Hazardous materials (substances) which may be found at the site may include drilling mud and cementing products which are primarily inhalation hazards, fuels (flammable and/or combustible), materials that may be necessary for well completion/ stimulation activities such as flammable or combustible substances and acids/gels (corrosives). The opportunity for Superfund Amendments and Reauthorization Act (SARA) listed Extremely Hazardous Substances (EHS) at the site is generally limited to proprietary treating chemicals. All hazardous and EHS and commercial preparations will be handled in an appropriate manner to minimize the potential for leaks or spills to the environment.

8. ANCILLARY FACILITIES:

None anticipated.

9. WELL SITE LAYOUT:

- A. Refer to attached well site plat for related topography cuts and fills and cross sections.
- B. Refer to attached well site plat for rig layout and soil material stockpile location as approved on On-site.
- C. Refer to attached well site plat for rig orientation, parking areas, and access road.

The reserve pit will be located on the east corner of the location. The flare pit will be located downwind of the prevailing wind direction on the west side of the location, a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled topsoil will be stored between Corners #5 and #6. Upon completion of construction, the stockpiled topsoil from the location will be broadcast seeded with the approved seed mixture from this location and then walked down with a Caterpillar tractor.

Access to the well pad will be from the south.

FENCING REQUIREMENTS:

All pits will be fenced according to the following minimum standards:

- A. Thirty-nine inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.)
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total height of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner as to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distances between any two posts shall be no greater than 16 feet.
- E. All wire shall be stretched by using a stretching device before it is attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and, upon completion

of construction, the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is regularly traveled. If the well is a producer, the cattleguards (shall/shall not) be permanently counted on concrete bases. Prior to crossing any fence located on Federal land, or any fence between Federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RECLAMATION OF THE SURFACE:

A. Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The stockpiled pit topsoil will then be spread over the pit area and broadcast seeded with the prescribed seed mixture for this location. The seeded area will then be walked down with a cat.

B. Dry Hole/Abandoned Location

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and the BLM will attach the appropriated surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP:

Surface ownership of the proposed well site, access road, and pipeline route is as follows:

State of Utah

12. OTHER INFORMATION:

- A. EOG Resources, Inc. will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the Authorized Officer. Within five working days the Authorized Officer will inform the operator as to:

- Whether the materials appear eligible for the National Register of Historic Places;
- The mitigation measures the operator will likely have to undertake before the site can be used.
- A time frame for the Authorized Officer to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the Authorized Officer are correct and that mitigation is appropriate.

If the operator wished, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the Authorized Officer will assume responsibility for whatever recordation and stabilization of the exposed materials that may be required. Otherwise, the operator will be responsible for mitigation costs. The Authorized Officer will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the Authorized Officer that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator, EOG Resources, Inc. will control noxious weeds along Right-of-Ways for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds will be obtained from the BLM administered land, a Pesticide Use proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.
- C. The drilling rig and ancillary equipment will be removed from the location prior to commencement of completion operations. Completion operations will be conducted utilizing a completion/workover rig.
- D. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on BLM lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice of Lessees. The operator is fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Construction activity will not be conducted using frozen or saturated soils material or during periods when watershed damage is likely to occur.

If the existing access road, proposed access road, and proposed pad are dry during construction, drilling, and completion activities, water will be applied to help facilitate compaction during construction and to minimize soil loss as a result of wind erosion.

LESSEE OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:

PERMITTING AGENT

Kaylene R. Gardner
EOG Resources, Inc.
P.O. Box 1815
Vernal, Ut 84078
(435) 781-9111


DRILLING OPERATIONS

Donald Presenkowski
EOG Resources, Inc.
P.O. Box 250
Big Piney, WY 83113
307-276-4865

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EOG Resources, Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Please be advised that EOG Resources, Inc. is considered to be the operator of the Chapita Wells Unit 722-32 Well, located in the NESE, of Section 32, T9S, R23E, Uintah County, Utah; Federal land and minerals; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond Coverage is under Bond # NM 2308.

November 10, 2006
Date


Kaylene R. Gardner Regulatory Assistant

EOG RESOURCES, INC.

CWU #722-32

LOCATED IN UINTAH COUNTY, UTAH
SECTION 32, T9S, R23E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW OF EXISTING ACCESS

CAMERA ANGLE: NORTHEASTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

10 **31** **06**
MONTH DAY YEAR

PHOTO

TAKEN BY: GS.

DRAWN BY: C.P.

REVISED: 00-00-00

EOG RESOURCES, INC.
CWU #722-32
SECTION 32, T9S, R23E, S.L.B.&M.



PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 4.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.1 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.2 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.6 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.2 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN RIGHT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.1 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 54.4 MILES.

EOG RESOURCES, INC.

LOCATION LAYOUT FOR


CWU #722-32
SECTION 32, T9S, R23E, S.L.B.&M.
2071' FSL 713' FEL




SCALE: 1" = 50'
DATE: 10-27-06
Drawn By: S.L.

NOTE:

Flare Pit is to be located
a min. of 100' from the
Well Head.



UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017



LEGEND:

● PROPOSED LOCATION

EOG RESOURCES, INC.

CWU #722-32

SECTION 32, T9S, R23E, S.L.B.&M.

2071' FSL 713' FEL



Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC
MAP


10 31 06
MONTH DAY YEAR

SCALE: 1:100,000

DRAWN BY: C.P.

REVISED: 00-00-00





LEGEND:

— EXISTING ROAD



EOG RESOURCES, INC.

CWU #722-32
SECTION 32, T9S, R23E, S.L.B.&M.
2071' FSL 713' FEL



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813


TOPOGRAPHIC
MAP

10 31 06
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00



R
23
E



PROPOSED LOCATION:
CWU #722-32

T9S
T10S

LEGEND:

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED



EOG RESOURCES, INC.

CWU #722-32
SECTION 32, T9S, R23E, S.L.B.&M.
2071' FSL 713' FEL



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

10 31 06
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00



**WORKSHEET
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 11/14/2006

API NO. ASSIGNED: 43-047-38862

WELL NAME: CWU 722-32

OPERATOR: EOG RESOURCES INC (N9550)

CONTACT: KAYLENE GARDNER

PHONE NUMBER: 435-789-0790

PROPOSED LOCATION:

NESE 32 090S 230E

SURFACE: 2071 FSL 0713 FEL

BOTTOM: 2071 FSL 0713 FEL

COUNTY: UINTAH

LATITUDE: 39.99100 LONGITUDE: -109.3432

UTM SURF EASTINGS: 641452 NORTHINGS: 4427863

FIELD NAME: NATURAL BUTTES (630)

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	<i>o/ed</i>	1/8/07
Geology		
Surface		

LEASE TYPE: 3 - State

LEASE NUMBER: ML 3355

SURFACE OWNER: 3 - State

PROPOSED FORMATION: NHORN

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[] Ind[] Sta[] Fee[]
(No. 6196017)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. 49-1501)
☒ RDCC Review (Y/N)
(Date: _____)
☒ Fee Surf Agreement (Y/N)
☒ Intent to Commingle (Y/N)

LOCATION AND SITING:


____ R649-2-3.
Unit: CHAPITA WELLS
____ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
____ R649-3-3. Exception
☒ Drilling Unit
Board Cause No: 179.8
Eff Date: 8-18-1999
Siting: Suspends General Siting
____ R649-3-11. Directional Drill

COMMENTS:

Needs Permit (12-13-06)

STIPULATIONS:

*1- STATEMENT OF BASIS
2- Surf-Csg Cont Stip
3- Cement Stip #3 (4 1/2" production, 2000' min)*



OPERATOR: EOG RESOURCES INC (N9550)

SEC: 32 T.9S R. 23E

FIELD: NATURAL BUTTES (630)

COUNTY: UINTAH

CAUSE: 179-8 / 8-10-1999

Field Status


- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Wells Status

- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL
- DRILLING



Utah Oil Gas and Mining



PREPARED BY: DIANA MASON
DATE: 21-NOVEMBER-2006

Application for Permit to Drill

Statement of Basis

12/14/2006

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Ownr	CBM
173	43-047-38862-00-00		GW	S	No
Operator	EOG RESOURCES INC		Surface Owner-APD		
Well Name	CWU 722-32		Unit		
Field	UNDESIGNATED		Type of Work		
Location	NESE 32 9S 23E S 0 F L 0 F L GPS Coord (UTM) 641452E 4427863N				

Geologic Statement of Basis

EOG proposes to set 2,300 feet of surface casing cemented to the surface. The base of the moderately saline ground water is estimated at 3,200 feet. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of section 32. The surface formation at this location is the Uinta Formation. The Uinta Formation is made up of discontinuous sands interbedded with shales which are not expected to be prolific aquifers. It is recommended that the surface casing be extended to cover the base of the moderately saline ground water.

Brad Hill

11/14/2006

APD Evaluator

Date / Time

Surface Statement of Basis

This is a twin well planned on an existing location of the CWU #852-32 producing gas well. The existing pad will be slightly enlarged.

Floyd Bartlett

12/13/2006

Onsite Evaluator

Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator EOG RESOURCES INC
Well Name CWU 722-32
API Number 43-047-38862-0 **APD No** 173 **Field/Unit** UNDESIGNATED
Location: 1/4,1/4 NESE **Sec** 32 **Tw** 9S **Rng** 23E 0 FL 0 FL
GPS Coord (UTM) 641452 4427860 **Surface Owner**

Participants

Floyd Bartlett (DOGM), Byron Tolman (Permit Agent for EOR Resources), Beh Williams (DWR)

Regional/Local Setting & Topography

On existing pad with CWU #852-32.

Surface Use Plan

Current Surface Use

Existing Well Pad

Wildlife Habitat

Grazing

New Road

Miles	Well Pad	Src Const Material	Surface Formation
0	Width 261 Length 325	Onsite	

Ancillary Facilities N

Waste Management Plan Adequate? Y

Environmental Parameters

Affected Floodplains and/or Wetland N

Flora / Fauna

Existing pad that pit has been colsed. No vegetation established.

Soil Type and Characteristics

sandy loam with rock below the surface.

Erosion Issues N

Sedimentation Issues N

Site Stability Issues N

Drainage Diverson Required N

Berm Required? N

Erosion Sedimentation Control Required? N

Reserve Pit

Site-Specific Factors		Site Ranking
Distance to Groundwater (feet)	>200	0
Distance to Surface Water (feet)	>1000	0
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)	<300	20
Native Soil Type	Mod permeability	10
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)	<10	0
Affected Populations	<10	0
Presence Nearby Utility Conduits	Not Present	0
Final Score		35 1 Sensitivity Level

Characteristics / Requirements

Reserve pit will be in same location as previous pit in an area of cut. Dimensions are 147' x 75' x 12' deep. A liner is planned.

Closed Loop Mud Required? Liner Required? Y Liner Thickness 16 Pit Underlayment Required? Y


Other Observations / Comments

Ben Williams representing the DWR had no concerns. Jim Davis of SITLA was invited but did not attend.

Floyd Bartlett
Evaluator

12/13/2006
Date / Time

Casing Schematic



Well name:
Operator: **EOG Resources Inc.**
String type: **Surface**
Location: **Uintah County**

2006-12 EOG CWU 722-32

Project ID:
43-047-38862

Design parameters:

Collapse

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 107 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 290 ft

Cement top: 801 ft

Burst

Max anticipated surface pressure: 2,024 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 2,300 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.

Neutral point: 2,014 ft

Non-directional string.

Re subsequent strings:

Next setting depth: 6,500 ft
Next mud weight: 9.500 ppg
Next setting BHP: 3,208 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 2,300 ft
Injection pressure: 2,300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2300	9.625	36.00	J-55	ST&C	2300	2300	8.796	998.3
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1004	2020	2.013	2300	3520	1.53	73	394	5.43 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Minerals

Phone: 801-538-5357
FAX: 801-359-3940

Date: January 4, 2007
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 2300 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:
 Operator: **EOG Resources Inc.**
 String type: Production
 Location: Uintah County

2006-12 EOG CWU 722-32

Project ID:
 43-047-38862

Design parameters:

Collapse

Mud weight: 9.500 ppg
 Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
 Surface temperature: 75 °F
 Bottom hole temperature: 166 °F
 Temperature gradient: 1.40 °F/100ft
 Minimum section length: 1,500 ft

Cement top: 3,929 ft

Burst

Max anticipated surface pressure: 1,778 psi
 Internal gradient: 0.220 psi/ft
 Calculated BHP 3,208 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
 8 Round LTC: 1.80 (J)
 Buttress: 1.60 (J)
 Premium: 1.50 (J)
 Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.
 Neutral point: 5,577 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	6500	4.5	11.60	P-110	LT&C	6500	6500	3.875	567.2
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	3208	7580	2.363	3208	10690	3.33	65	279	4.31 J

Prepared by: Helen Sadik-Macdonald
 Div of Oil, Gas & Minerals

Phone: 801-538-5357
 FAX: 801-359-3940

Date: January 4, 2007
 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 6500 ft, a mud weight of 9.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

November 22, 2006

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2006 Plan of Development Chapita Wells Unit Uintah
County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following well is planned for calendar year 2006 within the Chapita Wells Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
-------	-----------	----------

(Proposed PZ Wasatch)

43-047-38862 CWU 722-32 Sec 32 T09S R23E 2071 FSL 0713 FEL

This office has no objection to permitting the well at this time.

/s/ Michael L. Coulthard

bcc: File - Chapita Wells Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:11-22-06



EOG Resources, Inc.
1060 E Hwy 40
Vernal, Utah 84078

January 3, 2007

Utah Department of Oil Gas & Mining
Atten: Diana Mason
P.O. Box 145801
Salt Lake City, UT 84114-5801

**RE: Revised Drilling Plan
Chapita Wells Unit 722-32
NE/SE, Section 32-T9S-R23E
Lease: ML 3355**

Dear Diana:

Enclosed please find a Revised Drilling Plan, detailing cement for the surface hole procedure, for the above referenced well.

Please contact me at 435-781-9111 if you have any additional questions concerning this matter.

Sincerely,

A handwritten signature in black ink, appearing to read "Kaylene R. Gardner", written over a horizontal line.

Kaylene R. Gardner
Sr. Regulatory Assistant

cc: File

RECEIVED

JAN 04 2007

DIV. OF OIL, GAS & MINING

Revised: EIGHT POINT PLAN

CHAPITA WELLS UNIT 722-32
NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

1. & 2 ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	TVD-RKB (ft)	Objective	Lithology	
Green River	1,355		Shale	Oil / Gas
Wasatch	4,289	Primary	Sandstone	Gas
Chapita Wells	4,824	Primary	Sandstone	Gas
Buck Canyon	5,510	Primary	Sandstone	Gas
North Horn	6,109	Primary	Sandstone	Gas
KMV Price River	6,331	Primary	Sandstone	Gas
TD	9,800			

EST. TD: 6,500' or 200' ± below Island Top

Anticipated BHP: 3,210 Psig

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

3. PRESSURE CONTROL EQUIPMENT:

Production Hole – 5000 Psig
BOP schematic diagrams attached.

4. CASING PROGRAM:

CASING	Hole Size	Length	Size	WEIGHT	Grade	Thread	Rating Collapse	Factor Burst	Tensile
Cond.	17 ½"	0 – 45'	13 ¾"	48.0#	H-40	STC	770 PSI	1730 PSI	322,000#
Surface	12 ¼"	45' – 2,300' KB±	9-5/8"	36.0#	J-55	STC	2020 PSI	3520 Psi	394,000#
Prod	7-7/8"	2,300'± – TD	4-½"	11.6#	P-110	LTC	7560 PSI	10,710 Psi	284,000#

Note: 12-¼" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-5/8" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.

All casing will be new or inspected.

RECEIVED
JAN 04 2007

CHAPITA WELLS UNIT 722-32
NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

5. Float Equipment:

Surface Hole Procedure (0' - 2300'±)

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-½", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. (30± total). Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (Surface - 2300'±):

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD): Anticipated mud weight 9.0 – 9.5 ppg depending on actual wellbore conditions encountered while drilling.

2300'± - TD A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Defloculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

7. VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 2 – Item E: Special Drilling Operations

EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. Due to reduce location excavation, the blooie line will be approximately 75' in length

CHAPITA WELLS UNIT 722-32
NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

8. EVALUATION PROGRAM:

Logs: Mud log from base of surface casing to TD.
Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following:
Cement Bond / Casing Collar Locator and Pulsed Neutron

9. CEMENT PROGRAM:

Surface Hole Procedure (Surface - 2300'±):

Lead: 185 sks Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.

Tail: 207 sks Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Top Out: As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Note: Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

Production Hole Procedure (2300'± - TD)

Lead: 110 sks: 35:65 Poz "G" w/4% D20 (Bentonite), 2% D174 (Extender), 0.2% D65 (Dispersant), 0.2% D46 (Antifoam), 0.75% D112 (Fluid Loss Additive), 0.200% D13 (Retarder), 0.25 pps D29 (cello flakes) mixed at 13.0 ppg, 1.75 ft³/sk., 9.19 gps water.

Tail: 480 sks: 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9gps water.

Note: The above number of sacks is based on gauge-hole calculation.
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

Final Cement volumes will be based upon gauge-hole plus 45% excess.

CHAPITA WELLS UNIT 722-32
NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

10. ABNORMAL CONDITIONS:

Surface Hole (Surface - 2300'±):

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

(Attachment: BOP Schematic Diagram)

From: Ed Bonner
To: Mason, Diana
Date: 1/18/2007 2:13 PM
Subject: Well Clearance

CC: Davis, Jim; Garrison, LaVonne; Hill, Brad; Hunt, Gil
The following wells have been given cultural resource clearance by the Trust Lands Cultural Resources Group:

EOG Resources, Inc
Chapita Wells Unit 722-32 (API 43 047 38862)

Enduring Resources, LLC
Long Draw 12-24-34-23 (API 43 047 38652)

Gasco Production Company
Wilkin Ridge State 21-16-10-17 (API 43 047 38883)
Wilkin Ridge State 32-32-10-17 (API 43 047 38882)
Wilkin Ridge State 11-32-10-17 (API 43 047 38875)

Wind River II Corporation
Snowshoe 4-15-16-22 (API 43 019 31510)

If you have any questions regarding this matter please give me a call.



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

January 18, 2007

EOG Resources, Inc.
P O Box 1815
Vernal, UT 84078

Re: Chapita Wells Unit 722-32 Well, 2071' FSL, 713' FEL, NE SE, Sec. 32,
T. 9 South, R. 23 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-38862.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor (via e-mail)
Bureau of Land Management, Vernal District Office
SITLA

Operator: EOG Resources, Inc.
Well Name & Number Chapita Wells Unit 722-32
API Number: 43-047-38862
Lease: ML-3355

Location: NE SE **Sec.** 32 **T.** 9 South **R.** 23 East

Conditions of Approval

1. **General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. **Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. **Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

Page 2
43-047-38862
January 18, 2007

6. Surface casing shall be cemented to the surface.
7. Cement volume for the 4 1/2" production string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to 2100' MD as indicated in the submitted drilling plan.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML3355
2. NAME OF OPERATOR: EOG Resources, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Chapita Wells Unit
3. ADDRESS OF OPERATOR: 1060 East Highway 40 CITY Vernal STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: Chapita Wells Unit 722-32
PHONE NUMBER: (435) 781-9111		8. WELL NAME and NUMBER: Chapita Wells Unit 722-32
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2071 FSL - 713 FEL 39.990914 LAT 109.343875 LON		9. API NUMBER: 43-047-38862
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 9S 23E S		10. FIELD AND POOL, OR WILDCAT: Natural Buttes
COUNTY: Uintah		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: APD Extension
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Resources, Inc. requests the APD for the referenced well be extended for one year.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 01-23-2008
By: [Signature]

COPY SENT TO OPERATOR

Date: 1-24-2008

Initials: KS

NAME (PLEASE PRINT) Kaylene R. Gardner	TITLE Lead Regulatory Assistant
SIGNATURE [Signature]	DATE 1/15/2008

(This space for State use only)

RECEIVED
JAN 22 2008

DIV. OF OIL, GAS & MINING

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 43-047-38862
Well Name: Chapita Wells Unit 722-32
Location: 2071 FSL - 713 FEL (NESE), SECTION 32, T9S, R23E S.L.B.&M
Company Permit Issued to: EOG RESOURCES, INC.
Date Original Permit Issued: 1/18/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☐

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒


Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐


Signature

1/15/2008

Date

Title: Lead Regulatory Assistant

Representing: EOG Resources, Inc.

RECEIVED

JAN 22 2008

DIV. OF OIL, GAS & MINING

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: EOG RESOURCES INC

Well Name: CWU 722-32

Api No: 43-047-38862 Lease Type: STATE

Section 32 Township 09S Range 23E County UINTAH

Drilling Contractor CRAIG'S ROUSTABOUT SERV RIG # RATHOLE

SPUDDED:

Date 05/12/08

Time 3:30 PM

How DRY

Drilling will Commence: _____

Reported by JERRY BARNES

Telephone # (435) 828-1720

Date 05/13//08 Signed CHD

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3355
2. NAME OF OPERATOR: EOG Resources, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1060 East Highway 40 CITY Vernal STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: Chapita Wells Unit
PHONE NUMBER: (435) 789-0790		8. WELL NAME and NUMBER: Chapita Wells Unit 722-32
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2071' FSL & 713' FEL 39.990914 LAT 109.343875 LON		9. API NUMBER: 43-047-38862
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 9S 23E		10. FIELD AND POOL, OR WILDCAT: Natural Buttes
COUNTY: Uintah		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Respectfully requests authorization to change the drilling plan for the referenced well.

A revised drilling plan is attached.

COPY SENT TO OPERATOR

Date: 5.19.2008

Initials: KS

NAME (PLEASE PRINT) Kaylene R. Gardner

TITLE Lead Regulatory Assistant

SIGNATURE Kaylene R. Gardner

DATE 5/7/2008

(This space for State use only)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

DATE: 5/19/08

BY: [Signature] (See Instructions on Reverse Side)

*Surface Casing shall be cemented back to surface

RECEIVED

MAY 09 2008

DIV. OF OIL, GAS & MINING

DRILLING PLAN

CHAPITA WELLS UNIT 722-32 NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.. UINTAH COUNTY, UTAH

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	TVD-RKB (ft)	Objective	Lithology	
Green River	1,355		Shale	
Wasatch	4,289	Primary	Sandstone	Gas
Chapita Wells	4,824	Primary	Sandstone	Gas
Buck Canyon	5,510	Primary	Sandstone	Gas
North Horn	6,109	Primary	Sandstone	Gas
KMV Price River	6,349		Sandstone	
TD	6,500			

Estimated TD: 6,500' or 200'± below TD

Anticipated BHP: 3,550 Psig

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

3. PRESSURE CONTROL EQUIPMENT:

Production Hole – 5000 Psig
BOP schematic diagrams attached.

4. CASING PROGRAM:

CASING	Hole Size	Length	Size	WEIGHT	Grade	Thread	Rating Collapse	Factor Burst	Tensile
Conductor	17 ½"	0 – 45'	13 ⅝"	48.0#	H-40	STC	770 PSI	1730 PSI	322,000#
Surface	12 ¼"	0' – 2,300' KB±	9-⅝"	36.0#	J-55	STC	2020 PSI	3520 Psi	394,000#
Production	6-¼"	Surface – TD	4-½"	11.6#	P-110	BTC	7560 PSI	10,690 Psi	279,000#

Note: 12-¼" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-⅝" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.

All casing will be new or inspected.

DRILLING PLAN
CHAPITA WELLS UNIT 722-32
NE/SE, SEC. 32, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

5. Float Equipment:

Surface Hole Procedure (0' - 2300'±)

Guide Shoe
Insert Float Collar (PDC drillable)
Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

Production Hole Procedure (2300'± - TD):

Bit, Cross-over sub with float, IB stabilizer, Casing pup jt., IB Stabilizer, 1 joint casing, and balance of casing to surface. All casing will be 4-½", 11.6#, P-110, Buttress and Grant Prideco DWC couplings, with a marker jt. 400' above top of Wasatch. Composite-coated, positive stand-off centralizers will be utilized on the bottom 20 jts. The casing will be rotated via a top-drive system to drill the hole. A cement plug will be landed on the float above the bit.

6. MUD PROGRAM

Surface Hole Procedure (Surface - 2300'±):

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD):

Anticipated mud weight 9.5 – 10.5 ppg depending on actual wellbore conditions encountered while drilling.

2300'± - TD A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

DRILLING PLAN
CHAPITA WELLS UNIT 722-32
NE/SE, SEC. 32, T9S, R23E, S.L.B.&M..
UINTAH COUNTY, UTAH

7. VARIANCE REQUESTS:

Reference: **Onshore Oil and Gas Order No. 1**
 Onshore Oil and Gas Order No. 2 – Section E: Special Drilling Operations

- EOG Resources, Inc. requests a variance to regulations requiring a straight run blooie line to be 100' in length. (Where possible, a straight run blooie line will be used).
- EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. To reduce location excavation, the blooie line will be approximately 75' in length.
- EOG Resources, Inc. requests a variance to regulations, during air drilling operations only, requiring dedusting equipment. Dust during air drilling operations is controlled by water mist.
- EOG Resources, Inc. requests a variance to regulations, during air drilling operations only, requiring an automatic igniter or continuous pilot light on the blooie line. (Not required on aerated water system).
- EOG Resources, Inc. requests a variance that compressors are located in the opposite direction from the blooie line a minimum of 100 feet from the well bore. (Air Compressors are rig mounted).

8. EVALUATION PROGRAM:

Logs: Gas shows from base of surface casing to TD.

Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following: **Cement Bond / Casing Collar Locator and Pulsed Neutron**

DRILLING PLAN

CHAPITA WELLS UNIT 722-32 NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.. UINTAH COUNTY, UTAH

9. CEMENT PROGRAM:

Surface Hole Procedure (Surface - 2300'±):

- Lead: 185 sks** Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.
- Tail: 207 sks** Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.
- Top Out:** As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.
- Note:** Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

Production Hole Procedure (2300'± - TD)

- Lead: 80 sks:** Hi-Lift "G" w/12% D20 (Bentonite), 1% D79 (Extender), 5% D44 (Salt), 0.2% D46 (Antifoam), 0.25% D112 (Fluid Loss Additive), 0.25 pps D29 (cello flakes) mixed at 11.0 ppg, 3.91 ft³/sk., 24.5 gps water.
- Tail: 220 sks:** 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9gps water.
- Note:** The above number of sacks is based on gauge-hole calculation.
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.

Final Cement volumes will be based upon gauge-hole plus 45% excess.

10. ABNORMAL CONDITIONS:

Surface Hole (Surface - 2300'±):

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

This section of hole will be casing drilled and will meet BLM requirement for .422 of cement sheath space on all sides of the casing couplings.

DRILLING PLAN

CHAPITA WELLS UNIT 722-32 **NE/SE, SEC. 32, T9S, R23E, S.L.B.&M..** **UINTAH COUNTY, UTAH**

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

13. Air Drilling Operations:

- 1. Main Air Compressors are 1250 CFM 350 psi with 2000 psi Boosters and are rig mounted.
- 2. Secondary Air Compressors are 1170 CFM 350 psi with 2000 psi Boosters and are rig mounted.
- 3. Minimum setting depth of conductor casing will be 60' GL or 10'± into competent formation, whichever is deeper, as determined by the EOG person in charge. Exceptions must be approved by an EOG drilling superintendent or manager.
- 4. The diameter of the diverter flow line will be a minimum of 10" to help reduce back pressure on the well bore during uncontrolled flow.
- 5. Rat and Mouse hole drilling will occur only after surface casing has been set and cemented.
- 6. EOG Resources, Inc. will use a properly maintained and lubricated stripper head.

(Attachment: BOP Schematic Diagram)

BOPE REVIEW

EOG CWU 722-32 API 43-047-38862

INPUT

Well Name

Casing Size (")

Setting Depth (TVD)

Previous Shoe Setting Depth (TVD)

Max Mud Weight (ppg)

BOPE Proposed (psi)

Casing Internal Yield (psi)

Operators Max Anticipated Pressure (psi)

EOG CWU 722-32 API 43-047-38862

String 1	String 2		
9 5/8	4 1/2		
2300	6500		
45	2300		
8.4	10.5		
500	5000		
3520	10690		
3550	10.5 ppg		


Calculations

	String 1	9 5/8 "	
Max BHP [psi]	.052*Setting Depth*MW =	1005	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	729	NO - O.K. Air drill
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	499	YES
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth) =	509	NO
Required Casing/BOPE Test Pressure		2300 psi	
*Max Pressure Allowed @ Previous Casing Shoe =		450 psi	

Calculations

	String 2	4 1/2 "	
Max BHP [psi]	.052*Setting Depth*MW =	3549	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	2769	YES ✓
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	2119	YES
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth) =	2625	NO O.K.
Required Casing/BOPE Test Pressure		5000 psi	
*Max Pressure Allowed @ Previous Casing Shoe =		2300 psi	*Assumes 1psi/ft frac gradient

Casing Schematic



Well name:

2008-05 EOG CWU 722-32(rev2006-12)

Operator: EOG Resources Inc.

String type: Surface

Project ID:

43-047-38862

Location: Uintah County

Design parameters:**Collapse**

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor ~~1.125~~
1.325

Burst:

Design factor ~~1.00~~
1.20

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 107 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 290 ft

Cement top: 801 ft

Burst

Max anticipated surface pressure: 2,024 psi
Internal gradient: 0.120 psi/ft
Calculated BHP: 2,300 psi

No backup mud specified.

Tension:

8 Round STC: ~~1.80 (J)~~ 2.0
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 2,014 ft

Non-directional string.**Re subsequent strings:**

Next setting depth: 6,500 ft
Next mud weight: 10,500 ppg
Next setting BHP: 3,545 psi
Fracture mud wt: 19,250 ppg
Fracture depth: 2,300 ft
Injection pressure: 2,300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2300	9.625	36.00	J-55	ST&C	2300	2300	8.796	998.2
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1004	2020	2.013	2300	3520	1.53	72	394	5.43 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Minerals

Phone: 801-538-5357
FAX: 801-359-3940

Date: May 14, 2008
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 2300 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	2008-05 EOG CWU 722-32(rev2006-12)	
Operator:	EOG Resources Inc.	Project ID:
String type:	Production	43-047-38862
Location:	Uintah County	

Design parameters:
Collapse

Mud weight: 10.500 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor ~~1.125~~
1.325

Burst:

Design factor ~~4.00~~
1.20

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 166 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: 2,709 ft

Burst

Max anticipated surface pressure: 2,115 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 3,545 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: ~~4.00 (J)~~ 1.80
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.
Neutral point: 5,480 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	6500	4.5	11.60	P-110	Buttress	6500	6500	3.875	567.2
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	3545	7580	2.138	3545	10690	3.02	64	367	5.78 B

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Minerals

Phone: 801-538-5357
FAX: 801-359-3940

Date: May 14, 2008
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 6500 ft, a mud weight of 10.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: EOG Resources, Inc. Operator Account Number: N 9550
Address: 600 17th St., Suite 1000N
city Denver
state CO zip 80202 Phone Number: (303) 824-5526

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-38510	Natural Buttes Unit 573-17E		SESE	17	10S	21E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
B	99999	2900	5/9/2008			5/29/08	
Comments: <u>Wasatch/Mesaverde well</u>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-37512	Natural Buttes Unit 561-17E		SWSE	17	10S	21E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
B	99999	2900	5/9/2008			5/29/08	
Comments: <u>Wasatch/Mesaverde well</u>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-38862	Chapita Wells Unit 722-32		NESE	32	9S	23E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
EA	99999	16862	5/12/2008			5/29/08	
Comments: <u>Wasatch well</u>							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Mary A. Maestas

Name (Please Print)

Mary A. Maestas

Signature

Regulatory Assistant

Title

5/13/2008

Date

RECEIVED

MAY 13 2008

(5/2000)

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3355
2. NAME OF OPERATOR: EOG Resources, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 600 17th St., Suite 1000N CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME: Chapita Wells Unit
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2071' FSL & 713' FEL 39.990914 LAT 109.343875 LON		8. WELL NAME and NUMBER: Chapita Wells Unit 722-32
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 9S 23E S.L.B. & M.		9. API NUMBER: 43-047-38862
COUNTY: Uintah		10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Wasatch
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Well spud</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The referenced well spud on 5/12/2008.

NAME (PLEASE PRINT) <u>Mary A. Maestas</u>	TITLE <u>Regulatory Assistant</u>
SIGNATURE <u>Mary A. Maestas</u>	DATE <u>5/13/2008</u>

(This space for State use only)

RECEIVED

MAY 15 2008

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3355
2. NAME OF OPERATOR: EOG Resources, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 600 17th St., Suite 1000N CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME: Chapita Wells Unit
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2071' FSL & 713' FEL 39.990914 LAT 109.343875 LON		8. WELL NAME and NUMBER: Chapita Wells Unit 722-32
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 9S 23E S.L.B. & M.		9. API NUMBER: 43-047-38862
COUNTY: Uintah		10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Wasatch
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input checked="" type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Resources, Inc. requests authorization for disposal of produced water from the referenced well to any of the following locations.

1. Natural Buttes Unit 21-20B SWD
2. Chapita Wells Unit 550-30N SWD
3. Chapita Wells Unit 2-29 SWD
4. Red Wash Evaporation ponds 1, 2, 3 & 4
5. RN Industries

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

NAME (PLEASE PRINT) <u>Mary A. Maestas</u>	TITLE <u>Regulatory Assistant</u>
SIGNATURE <u>Mary A. Maestas</u>	DATE <u>5/13/2008</u>

(This space for State use only)

**RECEIVED
MAY 15 2008**

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3355
2. NAME OF OPERATOR: EOG Resources, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Chapita Wells Unit
3. ADDRESS OF OPERATOR: 600 17th St., Suite 1000N CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME: Chapita Wells Unit
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2071' FSL & 713' FEL 39.990914 LAT 109.343875 LON QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 9S 23E S.L.B. & M.		8. WELL NAME and NUMBER: Chapita Wells Unit 722-32
PHONE NUMBER: (303) 824-5526		9. API NUMBER: 43-047-38862
COUNTY: Uintah		10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Wasatch
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EOG Resources, Inc. requests authorization to change the drilling plan for the referenced well.

A revised drilling plan is attached.

COPY SENT TO OPERATOR

Date: 6-24-2008
Initials: KS

RECEIVED

JUN 06 2008

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Mary A. Maestas	TITLE Regulatory Assistant
SIGNATURE <u>Mary A. Maestas</u>	DATE 6/5/2008

(This space for State use only)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

DATE: 6/23/08

BY: Dustin

(See Instructions on Reverse Side)

* Cement shall be brought back to depths specified in plan

EIGHT POINT PLAN

CHAPITA WELLS UNIT 722-32 **NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.** **UINTAH COUNTY, UTAH**

1. & 2 ESTIMATED TOPS & ANTICIPATED OIL, GAS, & WATER ZONES:

FORMATION	DEPTH (KB)
Green River FM	1,355'
Wasatch	4,289'
Chapita Wells	4,824'
Buck Canyon	5,510'
North Horn	6,109'
Island	6,331'

EST. TD: 6,500' or 200' ± below Island Top

Anticipated BHP: 3,210 Psig

1. Fresh Waters may exist in the upper, approximately 1,000 ft ± of the Green River Formation, with top at about 2,000 ft ±.
2. Cement isolation is installed to surface of the well isolating all zones by cement.

3. PRESSURE CONTROL EQUIPMENT:

Production Hole – 5000 Psig
BOP schematic diagrams attached.

4. CASING PROGRAM:

	<u>HOLE SIZE</u>	<u>INTERVAL</u>	<u>SIZE</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>THREAD</u>	<u>RATING FACTOR</u>		
							<u>COLLAPSE</u>	<u>BURST</u>	<u>TENSILE</u>
Conductor:	17 ½"	0' – 45'	13 ⅝"	48.0#	H-40	STC	770 PSI	1730 PSI	322,000#
Surface	12-1/4"	45' – 2,300'KB±	9-5/8"	36.0#	J-55	STC	2020 PSI	3520 Psi	394,000#
Production:	7-7/8"	2,300'± – TD	4-½"	11.6#	N-80	LTC	6350 PSI	7780 Psi	223,000#

Note: 12-¼" surface hole will be drilled to a total depth of 200'± below the base of the Green River lost circulation zone and cased w/9-5/8" as shown to that depth. Drilled depth may be shallower or deeper than the 2300' shown above depending on the actual depth of the loss zone.
All casing will be new or inspected.

5. Float Equipment:

Surface Hole Procedure (0' - 2300'±)

Guide Shoe

Insert Float Collar (PDC drillable)

Centralizers: 1-5' above shoe, top of jts. #2 and #3 then every 5th joint to surface. (15 total)

EIGHT POINT PLAN
CHAPITA WELLS UNIT 722-32
NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

Float Equipment: (Cont'd)

Production Hole Procedure (2300'± - TD):

Float shoe, 1 joint casing, float collar and balance of casing to surface. 4-½", 11.6#, N-80 or equivalent marker collars or short casing joints to be placed at top of Price River and 400' above top of Wasatch. Centralizers to be placed 5' above shoe on joint #1, top of joint #2, and every 2nd joint to 400' above Wasatch Island top. (30± total). Thread lock float shoe, top and bottom of float collar, and top of 2nd joint.

6. MUD PROGRAM

Surface Hole Procedure (Surface - 2300'±):

Air/air mist or aerated water.

Production Hole Procedure (2300'± - TD): Anticipated mud weight 9.0 – 9.5 ppg depending on actual wellbore conditions encountered while drilling.

2300'± - TD A closed mud system will be utilized. A bentonite gelled water mud system will be used to control viscosity w/PHPA polymer used for supplemental viscosity and clay encapsulation/inhibition. Water loss will be maintained at <15cc's using white starch or PAC. Bactericides will be used as needed. Anticipated pH will range from 9.0-10.0. Mud weight will be adjusted as necessary for well control. Deflocculants/thinners will be used as necessary to maintain mud quality. LCM sweeps will be utilized as necessary to control lost circulation and mud loss. CO2 contamination, if encountered, will be treated with lime and gypsum.

7. VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 2 – Item E: Special Drilling Operations

EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. Due to reduce location excavation, the blooie line will be approximately 75' in length

8. EVALUATION PROGRAM:

Logs: Mud log from base of surface casing to TD.
Cased-hole Logs: Cased-hole logs will be run in lieu of open-hole logs consisting of the following:
Cement Bond / Casing Collar Locator and Pulsed Neutron

EIGHT POINT PLAN

CHAPITA WELLS UNIT 722-32 **NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.** **UINTAH COUNTY, UTAH**

9. CEMENT PROGRAM:

Surface Hole Procedure (Surface - 2300'±):

Lead: Class "G" cement with 16% Gel, 10 #/sx Gilsonite, 3% Salt, 2% CaCl₂, 3 lb/sx GR3 ¼ #/sx Flocele mixed at 11 ppg, 3.82 ft³/sk. yield, 23 gps water.

Tail: Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Top Out: As necessary with Class "G" cement with 2% CaCl₂, ¼#/sk Flocele mixed at 15.6 ppg, 1.18 ft³/sk., 5.2 gps water.

Note: Cement volumes will be calculated to bring lead cement to surface and tail cement to 500' above the casing shoe.

Production Hole Procedure (2300'± - TD)

Lead: 110 sks: 35:65 Poz "G" w/4% D20 (Bentonite), 2% D174 (Extender), 0.2% D65 (Dispersant), 0.2% D46 (Antifoam), 0.75% D112 (Fluid Loss Additive), 0.200% D13 (Retarder), 0.25 pps D29 (cello flakes) mixed at 13.0 ppg, 1.75 ft³/sk., 9.19 gps water.

Tail: 480 sks: 50:50 Poz "G" w/ 2% D20 (Bentonite), 0.1% D46 (Antifoam), 0.075% D13 (Retarder), 0.2% D167 (Fluid Loss Additive), 0.2% D65 (Dispersant), mixed at 14.1 ppg, 1.28 ft³/sk., 5.9gps water.

Note: The above number of sacks is based on gauge-hole calculation.
Lead volume to be calculated to bring cement to 200'± above 9-5/8" casing shoe.
Tail volume to be calculated to bring cement to 400'± above top of Wasatch.
Final Cement volumes will be based upon gauge-hole plus 45% excess.

10. ABNORMAL CONDITIONS:

Surface Hole (Surface - 2300'±):

Lost circulation

Production Hole (2300'± - TD):

Sloughing shales, lost circulation and key seat development are possible in the Wasatch Formation.

EIGHT POINT PLAN

CHAPITA WELLS UNIT 722-32
NE/SE, SEC. 32, T9S, R23E, S.L.B.&M.
UINTAH COUNTY, UTAH

11. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Upper and Lower Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

12. HAZARDOUS CHEMICALS:

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

(Attachment: BOP Schematic Diagram)

VARIANCE REQUESTS:

Reference: Onshore Oil and Gas Order No. 1
Onshore Oil and Gas Order No. 2 – Section E: Special Drilling
Operations

- EOG Resources, Inc. requests a variance to regulations requiring a straight run blooie line to be 100' in length. (Where possible, a straight run blooie line will be used).
- EOG Resources, Inc. requests a variance to regulations requiring the blooie line to be 100' in length. To reduce location excavation, the blooie line will be approximately 75' in length.
- EOG Resources, Inc. requests a variance to regulations, during air drilling operations only, requiring dedusting equipment. Dust during air drilling operations is controlled by water mist.
- EOG Resources, Inc. requests a variance to regulations, during air drilling operations only, requiring an automatic igniter or continuous pilot light on the blooie line. (Not required on aerated water system).
- EOG Resources, Inc. requests a variance that compressors are located in the opposite direction from the blooie line a minimum of 100 feet from the well bore. (Air Compressors are rig mounted).

AIR DRILLING OPERATIONS:

- Main Air Compressors are 1250 CFM 350 psi with 2000 psi Boosters and are rig mounted.
- Secondary Air Compressors are 1170 CFM 350 psi with 2000 psi Boosters and are rig mounted.
- Minimum setting depth of conductor casing will be 60' GL or 10'± into competent formation, whichever is deeper, as determined by the EOG person in charge. Exceptions must be approved by an EOG drilling superintendent or manager.
- The diameter of the diverter flow line will be a minimum of 10" to help reduce back pressure on the well bore during uncontrolled flow.
- Rat and Mouse hole drilling will occur only after surface casing has been set and cemented.
- EOG Resources, Inc. will use a properly maintained and lubricated stripper head.

Well name:

2008-05 EOG CWU 722-32(revII2006-12)Operator: **EOG Resources Inc.**String type: **Production**

Project ID:

43-047-38862Location: **Uintah County****Design parameters:****Collapse**

Mud weight: 10.500 ppg

Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No

Surface temperature: 75 °F

Bottom hole temperature: 166 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 1,500 ft

Cement top: 2,958 ft

Burst

Max anticipated surface pressure:

2,115 psi

Internal gradient:

0.220 psi/ft

Calculated BHP

3,545 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.

Neutral point: 5,480 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	6500	4.5	11.60	N-80	LT&C	6500	6500	3.875	567.2
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	3545	6350	1.791	3545	7780	2.19	64	223	3.51 J


Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & MineralsPhone: 801-538-5357
FAX: 801-359-3940Date: June 23, 2008
Salt Lake City, Utah**Remarks:**

Collapse is based on a vertical depth of 6500 ft, a mud weight of 10.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kernler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Casing Schematic



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
EOG Resources, Inc.

3. ADDRESS OF OPERATOR:
600 17th St., Suite 1000N CITY Denver STATE CO ZIP 80202

PHONE NUMBER:
(303) 824-5526

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 2071' FSL & 713' FEL 39.990914 LAT 109.343875 LON

COUNTY: Uintah

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 9S 23E S.L.B. & M.

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML-3355

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:
Chapita Wells Unit

8. WELL NAME and NUMBER:
Chapita Wells Unit 722-32

9. API NUMBER:
43-047-38862

10. FIELD AND POOL, OR WILDCAT:
Natural Buttes/Wasatch

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The referenced well was turned to sales on 8/26/2008. Please see the attached operations summary report for drilling and completion operations performed on the subject well.

NAME (PLEASE PRINT) Mary A. Maestas

TITLE Regulatory Assistant

SIGNATURE

DATE 9/2/2008

(This space for State use only)

RECEIVED

SEP 08 2008

DIV. OF OIL, GAS & MINING

WELL CHRONOLOGY REPORT

Report Generated On: 09-02-2008

Well Name	CWU 722-32	Well Type	DEVG	Division	DENVER
Field	CHAPITA WELLS UNIT	API #	43-047-38862	Well Class	ISA
County, State	UINTAH, UT	Spud Date	06-06-2008	Class Date	08-26-2008
Tax Credit	N	TVD / MD	6,500/ 6,500	Property #	059748
Water Depth	0	Last CSG	0.0	Shoe TVD / MD	5,131/ 5,131
KB / GL Elev	5,215/ 5,202				
Location	Section 32, T9S, R23E, NESE, 2071 FSL & 713 FEL				

Event No	1.0	Description	DRILL & COMPLETE		
Operator	EOG RESOURCES, INC	WI %	100.0	NRI %	82.5

AFE No	304228	AFE Total	1,303,300	DHC / CWC	694,700/ 608,600
Rig Contr	ELENBURG	Rig Name	ELENBURG #28	Start Date	11-16-2006
11-16-2006	Reported By	SHARON CAUDILL			
Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$0	Completion	\$0	Well Total	\$0
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: LOCATION DATA

Start	End	Hrs	Activity Description
-------	-----	-----	----------------------

06:00	06:00	24.0	LOCATION DATA 2071' FSL & 713' FEL (NE/SE) SECTION 32, T9S, R23E UINTAH COUNTY, UTAH
-------	-------	------	-----------------------------------------------------------------------------------------------

LAT 39.990947, LONG 109.343197 (NAD 27)
LAT 39.990914, LONG 109.343875 (NAD 83)

ELENBURG #28
OBJECTIVE: 6500' TD, NORTH HORN
DW/GAS
CHAPITA WELLS PROSPECT
DD&A: NATURAL BUTTES
NATURAL BUTTES FIELD

LEASE: ML 3355
ELEVATION: 5202' NAT GL, 5202' PREP GL (DUE TO ROUNDING THE PREP GL IS 5202'), 5215' KB (13')

EOG WI 100%, NRI 82.5%

05-06-2008 Reported By DAN/STEVE

Daily Costs: Drilling	\$38,000	Completion	\$0	Daily Total	\$38,000
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	START CONSTRUCTION OF LOCATION.

05-07-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION 20% COMPLETE.

05-08-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION IS 60% COMPLETE.

05-09-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION IS 75% COMPLETE.

05-12-2008 Reported By TERRY CSERE

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	0	TVD	0	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LINE TODAY. WEATHER PERMITTING.

05-13-2008 Reported By TERRY CSERE/KAYLENE GARDNER

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$38,000	Completion	\$0	Well Total	\$38,000
MD	60	TVD	60	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: BUILD LOCATION/SPUD NOTIFICATION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	LOCATION COMPLETE. - CRAIG'S ROUSTABOUT SERVICE SPUD A 20" HOLE ON 05/12/08 @ 3:30 PM. SET 60' OF 14" CONDUCTOR. CEMENT TO SURFACE WITH READY MIX. JERRY BARNES NOTIFIED CAROL DANIELS W/UDOGM & MICHAEL LEE W/BLM OF THE SPUD 05/12/08 @ 3:00 PM.

06-02-2008 Reported By JERRY BARNES

Daily Costs: Drilling	\$231,421	Completion	\$0	Daily Total	\$231,421
Cum Costs: Drilling	\$269,421	Completion	\$0	Well Total	\$269,421
MD	2,221	TVD	2,221	Progress	0
Days	0	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: WORT

Start	End	Hrs	Activity Description
06:00	06:00	24.0	MIRU ASPEN DRILLING RIG #14 ON 5/17/2008. DRILLED 12-1/4" HOLE TO 2237' GL. LOST RETURNS @ 560'. RAN 52 JTS (2208.81') OF 9-5/8", 36.0#, J-55, ST&C CASING WITH HALLIBURTON GUIDE SHOE AND FLOAT COLLAR. 8 CENTRALIZERS SPACED MIDDLE OF SHOE JOINT AND EVERY COLLAR TILL GONE. LANDED @ 2221' KB. RDMO ASPEN RIG.

MIRU HALLIBURTON CEMENTERS. HELD SAFETY MEETING. PRESSURE TESTED LINES AND CEMENT VALVE TO 1500 PSIG. PUMPED 172 BBLS FRESH WATER & 20 BBLS GELLED WATER FLUSH AHEAD OF CEMENT. MIXED & PUMPED 400 SX (84 BBLS) OF PREMIUM CEMENT W/2 % CACL2. MIXED CEMENT @ 15.6 PPG W/YIELD OF 1.18 CF/SX.

DISPLACED CEMENT W/169 BBLS FRESH WATER. BUMPED PLUG W/650# @ 7:40 PM, 5/21/2008. CHECKED FLOAT, FLOAT HELD. SHUT-IN CASING VALVE. NO RETURNS.

TOP JOB # 1: MIXED & PUMPED 100 SX (20.5 BBLS) OF PREMIUM CEMENT W/2 % CACL2. MIXED CEMENT @ 15.8 PPG W/YIELD OF 1.15 CF/SX. NO RETURNS. WOC 12 HRS. RDMO HALLIBURTON CEMENTERS.

TOP JOB # 2: MIRU HALLIBURTON CEMENTERS. MIXED & PUMPED 200 SX (41 BBLS) OF PREMIUM CEMENT W/2% CACL2. MIXED CEMENT @ 15.8 PPG W/YIELD OF 1.15 CF/SX. NO RETURNS. WOC 2 HRS.

TOP JOB # 3: MIXED & PUMPED 200 SX (41 BBLS) OF PREMIUM CEMENT W/2% CACL2. MIXED CEMENT TO 15.8 PPG W/YIELD OF 1.15 CF/SX. NO RETURNS. WOC 4 HRS.

TOP JOB # 4: MIXED & PUMPED 200 SX (41 BBLS) OF PREMIUM CEMENT W/2% CACL2. MIXED CEMENT @ 15.8 PPG W/YIELD OF 1.15 CF/SX. NO RETURNS. WOC 16 HRS 30 MINUTES. RDMO HALLIBURTON CEMENTERS.

TOP JOB # 5: MIRU HALLIBURTON CEMENTERS. MIXED & PUMPED 150 SX (30.7 BBLS) OF PREMIUM CEMENT W/2% CACL2. MIXED CEMENT @ 15.8 PPG W/YIELD OF 1.15 CF/SX. HOLE FILLED W/CEMENT & STOOD FULL. RDMO HALLIBURTON CEMENTERS.

PREPARED LOCATION FOR ROTARY RIG. WORT. WILL DROP FROM REPORT UNTIL FURTHER ACTIVITY.

ASPEN RIG 14 TOOK SURVEYS WHEN DRILLING HOLE @ 307' - 1.0°, 607' - 0.5°, 907' - 1.0°, 1207' - BULLS EYE, 1507' - 1.25°, 1807' - 1.0°, 2230' - 1.25°.

CONDUCTOR LEVEL RECORD: PS= 90.0 OPS= 90.0 VDS= 89.8 MS= 89.9.

9 5/8 CASING LEVEL RECORD: PS= 89.9 OPS= 90.0 VDS= 89.9 MS= 89.9.

LESTER FARNSWORTH NOTIFIED ROOSEVELT OFFICE W/UDOGM OF THE SURFACE CASING & CEMENT JOB ON 5/20/2008 @ 12:15 PM.

06-06-2008	Reported By	MATT WILLIAMS									
Daily Costs: Drilling	\$82,262	Completion	\$0	Daily Total	\$82,262						
Cum Costs: Drilling	\$351,683	Completion	\$0	Well Total	\$351,683						
MD	2,322	TVD	2,322	Progress	85	Days	1	MW	0.0	Visc	0.0
Formation :	PBTD : 0.0			Perf :	PKR Depth : 0.0						

Activity at Report Time: DRILLING @ 2322'

Start	End	Hrs	Activity Description
06:00	15:00	9.0	MOVE FROM CWU 698-32 TO CWU 722-32 & RIG UP. TRUCKS OFF LOCATION @ 12:00 NOON. INSTALL NIGHT CAP W/FMC.SETBOP AND TEST DTO HEAD W/ FMC & LOCK DOWN BOP.
15:00	19:00	4.0	NIPPLE UP BOP, ROT HEAD, CHOKE LINE, KILL LINE VALVES, HYD. HOSES, FUNCTION TEST BOP. RIG ON DAY WORK @ 15:00 HRS, 6/5/08.
19:00	22:00	3.0	TEST BOPE AS PER PROGRAM. NOTIFIED STATE REP, DAVID HACKFORD VERNAL OFFICE ON 6/05/08 @ 07:30 HRS FOR BOP TEST.

INSIDE BOP, SAFETY VALVE, UPPER KELLY COCK 250/5000 PSI 5/10 MIN.

HCR, CHOKE LINE, KILL LINE, 250/5000 PSI 5/10 MIN.

CHOKE MANIFOLD, 250/5000 PSI 5/10 MIN.

PIPE RAMS, BLIND RAMS, 250/5000 PSI 5/10 MIN.

ANNULAR, 250/2500 PSI 5/10 MIN.

TEST 9 5/8" CASING TO 1500 PSI 30 MIN.

WITNESS: DARYL DUNCAN

22:00	22:30	0.5	INSTALL WEAR BUSHING.
22:30	03:00	4.5	P/U AND TRIP IN HOLE WITH BHA. TAG @ 2130'.
03:00	04:00	1.0	DRILL CEMENT/FLOAT EQUIP F/2130' TO 2237' + 10' OF NEW HOLE TO 2247'.
04:00	04:30	0.5	CIRCULATE CLEAN.
04:30	05:00	0.5	FIT @ 2247', 190 PSI, 8.9 M/W = 10.5 EMW.
05:00	06:00	1.0	DRILLING FROM 2237' TO 2322', ROP 85, WOB 10/14, RPM 40, TQ 1200/1400.

MUD LOSS LAST 24 HRS. 0 BBLs.

MUD WT.8.9 VIS.29.

ROT 80, P/U 82, S/O 80.

ACCIDENTS NONE REPORTED.

FUNCTION CROWN-O-MATIC.

SAFETY MEETING: MOVING RIG, TESTING BOPE.

CREWS FULL.

FUEL ON HAND: 5424, GALS. USED: 213, GALS, REC. 4000 GAL.

GAS BG.40 U, CONN. 80 U.

LITHOLOGY: SHALE.

MUD LOGGER UNMANED ON LOCATION F/ 6/05/08 (1 DAY).

06:00 06:00 24.0 SPUD 7-7/8" HOLE @ 05:00 ON 6/06/08

06-07-2008 Reported By MATT WILLIAMS

Daily Costs: Drilling	\$27,470	Completion	\$0	Daily Total	\$27,470
------------------------------	----------	-------------------	-----	--------------------	----------

Cum Costs: Drilling	\$379,153	Completion	\$0	Well Total	\$379,153
----------------------------	-----------	-------------------	-----	-------------------	-----------

MD	4,677	TVD	4,677	Progress	2,355	Days	2	MW	8.9	Visc	28.0
-----------	-------	------------	-------	-----------------	-------	-------------	---	-----------	-----	-------------	------

Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0
--------------------	-------------------	---------------	------------------------

Activity at Report Time: DRILLING @ 4677'

Start	End	Hrs	Activity Description
06:00	12:30	6.5	DRILLING FROM 2322' TO 3319', ROP 153, WOB 12/18, RPM 40/50, TQ 1200/1800.
12:30	13:00	0.5	SERVICE RIG.
13:00	06:00	17.0	DRILLING FROM 3319' TO 4677', ROP 79, WOB 12/23, RPM 40/50, TQ 1200/2200.

MUD LOSS LAST 24 HRS. 0 BBLs.

MUD WT.9.1 VIS.32.

ROT 132, P/U 135, S/O 130.

ACCIDENTS NONE REPORTED.

FUNCTION CROWN-O-MATIC.

SAFETY MEETING: WORKING ON PUMPS, REPLACE FAN ON LIGHT PLANT.

CREWS FULL.

FUEL ON HAND: 4137, GALS. USED: 1287, GALS, REC, 0 GAL.

GAS BG.40 U, CONN. 80 U.

LITHOLOGY: SAND/SHALE.

MUD LOGGER UNMANED ON LOCATION F/ 6/05/08 (2 DAYS).

06-08-2008 Reported By MATT WILLIAMS

Daily Costs: Drilling	\$27,803	Completion	\$0	Daily Total	\$27,803
------------------------------	----------	-------------------	-----	--------------------	----------

Cum Costs: Drilling	\$406,956	Completion	\$0	Well Total	\$406,956
----------------------------	-----------	-------------------	-----	-------------------	-----------

MD	5,402	TVD	5,402	Progress	725	Days	3	MW	9.5	Visc	36.0
-----------	-------	------------	-------	-----------------	-----	-------------	---	-----------	-----	-------------	------

Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0
--------------------	-------------------	---------------	------------------------

Activity at Report Time: DRILLING @ 5402'

Start	End	Hrs	Activity Description
06:00	14:30	8.5	DRILLING FROM 4677' TO 5040', ROP 43, RPM 30/70, WOB 10/25, TQ 800/2200.
14:30	15:00	0.5	SERVICE RIG.
15:00	06:00	15.0	DRILLING FROM 5040 TO 5402', ROP 24, WOB 8/27, RPM 20/65, TQ 800/3000.

MUD LOSS LAST 24 HRS. 0 BBLs.

MUD WT.9.5 VIS.34.

ROT 132, P/U 140, S/O 135.

ACCIDENTS NONE REPORTED.

FUNCTION CROWN-O-MATIC.

SAFETY MEETING: WORKING ABOVE 6', OPERATING FORKLIFT.

CREWS FULL.

FUEL ON HAND: 2463, GALS. USED: 1674, GALS, REC, 0 GAL.

GAS BG.40 U, CONN. 80 U.

LITHOLOGY: SAND/SHALE.

MUD LOGGER UNMANED ON LOCATION F/ 6/05/08 (3 DAYS).

06-09-2008 **Reported By** MATT WILLIAMS

Daily Costs: Drilling	\$33,024	Completion	\$0	Daily Total	\$33,024
Cum Costs: Drilling	\$439,981	Completion	\$0	Well Total	\$439,981

MD 5,538 **TVD** 5,538 **Progress** 136 **Days** 4 **MW** 9.6 **Visc** 37.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: RIG REPAIR

Start	End	Hrs	Activity Description
06:00	11:30	5.5	DRILLING FROM 5402' TO 5538', ROP 24, WOB 10/28, RPM 20/65, TQ 600/2500.
11:30	12:30	1.0	SERVICE RIG.
12:30	15:00	2.5	C/O BOTH SWIVEL MOTORS.
15:00	16:00	1.0	CIRCULATE AND BUILD SLUG FOR TRIP OUT TO REPAIR SWIVEL.
16:00	20:00	4.0	TRIP OUT OF HOLE TO REPAIR SWIVEL.
20:00	21:00	1.0	REPAIR SLIPS.
21:00	23:30	2.5	CONTINUE TRIP OUT OF HOLE, L/D BHA TO REPAIR SWIVEL.
23:30	02:00	2.5	P/U AND TRIP IN HOLE W/ BHA TO 2121'.
02:00	06:00	4.0	REPAIR SWIVEL W/ ELENBURG MECHANICS.

MUD LOSS LAST 24 HRS. 0 BBLs.

MUD WT.9.6 VIS.36.

ROT 132, P/U 140, S/O 135.

ACCIDENTS NONE REPORTED.

FUNCTION CROWN-O-MATIC.

SAFETY: WORKING ON SWIVEL.

CREWS FULL.

FUEL ON HAND: 1112, GALS. USED: 1351, GALS, REC, 0 GAL.

GAS BG.40 U, CONN. 80 U.

LITHOLOGY: SAND/SHALE.

MUD LOGGER UNMANED ON LOCATION F/ 6/05/08 (4 DAYS).

06-10-2008 **Reported By** MATT WILLIAMS

Daily Costs: Drilling	\$60,524	Completion	\$0	Daily Total	\$60,524
Cum Costs: Drilling	\$500,505	Completion	\$0	Well Total	\$500,505

MD 5,542 **TVD** 5,542 **Progress** 4 **Days** 5 **MW** 9.6 **Visc** 37.0

Formation : **PBTD : 0.0** **Perf :** **PKR Depth : 0.0**

Activity at Report Time: TOH W/MILL

Start	End	Hrs	Activity Description
06:00	09:00	3.0	REPAIR SWIVEL.

09:00 12:30 3.5 TRIP IN HOLE FROM 2121' TO 5200'.

12:30 13:30 1.0 WASH/REAM FROM 5200' TO 5538'. (PREVIOUS PULLED BIT WAS MISSING ONE NOZZLE.) TAG BIT NOZZLE @ 5538'.

13:30 15:00 1.5 CIRCULATE AND CONDITION MUD. BUILD SLUG.

15:00 19:00 4.0 TRIP OUT OF HOLE WITH DRILL PIPE.

19:00 19:30 0.5 PULL ROTATING HEAD RUBBER.

19:30 20:30 1.0 LD BHA & TOOLS.

20:30 21:00 0.5 P/U BHA AND TOOLS, " MILL & JUNK BASKET".

21:00 02:00 5.0 TRIP IN HOLE TO 5493'.

02:00 03:30 1.5 REAM FROM 5493' TO 5538', WOM 2/3, RPM 40, TQ 800/1450.

03:30 04:30 1.0 MILL FROM 5538' TO 5542', WOM 2/10, RPM 40, TQ 800/1250.

04:30 05:30 1.0 PUMP SWEEP AND CIRCULATE HOLE CLEAN.

05:30 06:00 0.5 PUMP SLUG AND TRIP OUT OF HOLE.

MUD LOSS LAST 24 HRS. 0 BBLs.

MUD WT.9.7 VIS.36.

ROT 135, P/U 140, S/O 130.

ACCIDENTS NONE REPORTED.

FUNCTION CROWN-O-MATIC.

SAFETY: TRIPPING PIPE.

CREWS FULL.

FUEL ON HAND: 4137, GALS. USED: 475, GALS, REC, 3500 GAL.

GAS BG.40 U, CONN. 80 U.

LITHOLOGY: SAND/SHALE.

MUD LOGGER UNMANED ON LOCATION F/ 6/05/08 (5 DAYS).

06-11-2008 Reported By MATT WILLIAMS

Daily Costs: Drilling	\$34,531	Completion	\$0	Daily Total	\$34,531
Cum Costs: Drilling	\$535,037	Completion	\$0	Well Total	\$535,037

MD	6.170	TVD	6.170	Progress	628	Days	6	MW	9.8	Visc	37.0
----	-------	-----	-------	----------	-----	------	---	----	-----	------	------

Formation :	PBTD : 0.0	Perf :	PKR Depth : 0.0
-------------	------------	--------	-----------------

Activity at Report Time: DRILLING @ 6170'

Start	End	Hrs	Activity Description
06:00	11:00	5.0	TRIP OUT OF HOLE.
11:00	12:00	1.0	CLEAN OUT JUNK BASKET AND L/D.
12:00	14:30	2.5	P/U BHA AND TRIP IN HOLE TO 1810'.
14:30	16:00	1.5	SLIP & CUT DRILL LINE.
16:00	16:30	0.5	SERVICE RIG.
16:30	19:30	3.0	TRIP IN HOLE TO 5309'.
19:30	20:30	1.0	WASH AND REAM FROM 5309' TO 5542'.
20:30	06:00	9.5	DRILLING FROM 5542' TO 6170', ROP 66, WOB 15/21, RPM 40/45, TQ 1500/2100.

MUD LOSS LAST 24 HRS. 0 BBLs.

MUD WT.9.9 VIS.38.

ROT 147, P/U 1153, S/O 144.

ACCIDENTS NONE REPORTED.

FUNCTION CROWN-O-MATIC.

SAFETY: TRIPPING PIPE, OPERATING BOOM.

CREWS FULL.

FUEL ON HAND: 3347 GALS. USED: 790, GALS, REC, 0 GAL.

GAS BG.40 U, CONN. 80 U.

LITHOLOGY: SAND/SHALE.

MUD LOGGER UNMANNED ON LOCATION F/ 6/05/08 (6 DAYS).

06-12-2008 **Reported By** WILLIAMS/FOREMAN/SCHLENKER**Daily Costs: Drilling** \$30,466 **Completion** \$0 **Daily Total** \$30,466**Cum Costs: Drilling** \$565,503 **Completion** \$0 **Well Total** \$565,503**MD** 6,500 **TVD** 6,500 **Progress** 330 **Days** 7 **MW** 0.0 **Visc** 0.0**Formation :** **PBTD : 0.0** **Perf :** **PKR Depth : 0.0****Activity at Report Time:** RUNNING CASING @ 6500' TD

Start	End	Hrs	Activity Description
06:00	09:00	3.0	DRILLING F/6170' TO 6500' TD, ROP 94.2, WOB 20, RPM 45/72, TQ 1500/1800. REACHED TD AT 9:00 AM, 6/11/08.
09:00	12:30	3.5	CIRCULATE & COND MUD FROM 9.9 TO 10.5 FOR LAYING DOWN DRILL PIPE. NOTIFIED BY E-MAIL DAVID HACKFORD, STATE OF UTAH OF PENDING CASING AND CEMENT ON THIS WELL.
12:30	16:00	3.5	WIPER TRIP, CIRCULATE & SPOT 130 BBL 11.5 PILL ON BOTTOM.
16:00	22:30	6.5	LD DRILL PIPE & BHA, REMOVE WEAR BUSHING.
22:30	23:30	1.0	SAFETY MTG W/CASING CREW & RIG PERSONNEL, RIG UP WEATHERFORD TO RUN CASING.
23:30	06:00	6.5	RUN CASING W/WEATHERFORD, 136 JTS. 5400'

MUD LOST LAST 24 HRS.0 BBLs.

ACCIDENTS NONE REPORTED

FUNCTION TEST CROWN-O-MATIC,

SAFETY MEETING: RUNNING CASING

CREWS FULL

FUEL ON HAND: 2586 GAL USED 761 GAL

FORMATION: PRICE RIVER

LITHOLOGY: SAND/ SHALE,

MUD LOGGER UNMANNED ON LOCATION FROM 6/6/08 TO 6/11/08 (6 DAYS).

06-13-2008 **Reported By** D.FOREMAN/J.SCHLENKER**Daily Costs: Drilling** \$17,679 **Completion** \$107,942 **Daily Total** \$125,621**Cum Costs: Drilling** \$583,183 **Completion** \$107,942 **Well Total** \$691,125**MD** 6,500 **TVD** 6,500 **Progress** 0 **Days** 8 **MW** 0.0 **Visc** 0.0**Formation :** **PBTD : 0.0** **Perf :** **PKR Depth : 0.0****Activity at Report Time:** RDRT/WO COMPLETION

Start	End	Hrs	Activity Description
06:00	07:00	1.0	RUN CASING TAG @ 6500' RAN 160 JTS + 1 MARKER JT & 1 PUP JT 11.6#, N80, LTC, AS FOLLOWS, FLOAT SHOE, 1 JT CSG, FLOAT COLLAR, 63 JTS. CSG, 1 MARKER JT, 96 JTS. CSG, 1 PUP JT + HANGER ASS. FLOAT SHOE @ 6498', FLOAT COLLAR @ 6455', MARKER JT @ 3896', 12 CENTRALIZERS: 5 FT ABOVE SHOE, TOP OF JT #2 & EVERY 3RD JT TO 5205'.

07:00 08:30 1.5 LAY DOWN TAG JT, SPACE OUT HANGER, FILL CSG W/RIG PUMP, CIRC BOTTOMS UP & RIG DOWN WEATHERFORD, LAND CSG W/FULL STRING WT 66.000#. SAFETY MEETING W/SCHLUMBERGER & RIG CREW.

08:30 09:30 1.0 RIG UP SCHLUMBERGER. TEST LINES 5000 PSI, OKAY.

09:30 10:30 1.0 CEMENTING: PUMP 20 BBLs CHEM WASH & 20 BBLs WATER SPACER AHEAD OF LEAD AND CEMENT 6500' 4 1/2 N80 11.6# CSG. LEAD 240 SKS G + ADD. MIX D020 10.% EXTENDER, D167 .2% FLUID LOSS, D046 .2% ANTIFOAM, D013 .5% RETARDER, D065 .5% DISPERSANT, D130 .125LB/SK BLEND LOST CIRC. YIELD 2.98 CU FT/SK H2O 18.227 GAL/SK @ 11.5.PPG. TAIL 790 SKS 50/50 POZ G + ADDS: D020 2% EXTENDER, D046 .1% ANTIFOAM, D167 .2% FLUID LOSS, D065 .2% DISPERSANT, S001 1.% ACCELERATOR. YIELD 1.29 CUFT/SK H2O 5.96 GAL/SK @ 14.1 PPG. SHUT DOWN WASH OUT PUMPS & LINES. DROP TOP PLUG & DISP TO FLOAT COLLER W/FRESH WATER, 101 BBLs. AVG DISP RATE 7 BPM, FULL RETURNS THROUGHOUT JOB. DROP PLUG @ 10:07. BUMPED PLUG @ 10:27 TO 2500 PSI. 1000 PSI OVER LIFT PSI @ 1500, HOLD PRESS FOR 2 MINS. 1 BBL BACK, FLOAT HELD @ 10:29 CEMENT IN PLACE.

10:30 11:30 1.0 W/O CEMENT & RIG DOWN LINES.

11:30 12:00 0.5 REMOVE CEMENT HEAD & L/D LANDING JT.

12:00 13:00 1.0 INSTALL PACKOFF SEAL ASSEMBLY, UNLOCK BOP DTO HEAD W/ FMC REPL/D SERVICE TOOL.

13:00 18:00 5.0 CLEAN MUD TANKS & N/D BOP.

18:00 06:00 12.0 R/D & PREPARE FOR TRUCKS FOR 2.5 MILE RIG MOVE, SCHEDULED FOR 07:00 W/KHUR TRUCKING, RIG MAINT.

ADVISE DAVID HACKFORD & JAIME SPARGER @ 435-781-4502 OF BOP TEST.

06:00 06:00 24.0 RELEASE RIG @ 18:00 ON 6/12/2008
CASING POINT COST \$583,183

06-18-2008 **Reported By** SEARLE

Daily Costs: Drilling	\$0	Completion	\$39,535	Daily Total	\$39,535
Cum Costs: Drilling	\$583,183	Completion	\$147,477	Well Total	\$730,660

MD 6,500 **TVD** 6,500 **Progress** 0 **Days** 9 **MW** 0.0 **Visc** 0.0

Formation : **PBTD :** 6456.0 **Perf :** **PKR Depth :** 0.0

Activity at Report Time: WO COMPLETION

Start	End	Hrs	Activity Description
06:00	06:00	24.0	RU SCHLUMBERGER. RAN RST/CBL/VDL/GR/CCL FROM PBTD TO 50'. EST CEMENT TOP @ 310'. RD SCHLUMBERGER. WO COMPLETION.

06-26-2008 **Reported By** MCCURDY

Daily Costs: Drilling	\$0	Completion	\$1,723	Daily Total	\$1,723
Cum Costs: Drilling	\$583,183	Completion	\$149,200	Well Total	\$732,383

MD 6,500 **TVD** 6,500 **Progress** 0 **Days** 10 **MW** 0.0 **Visc** 0.0

Formation : **PBTD :** 6456.0 **Perf :** **PKR Depth :** 0.0

Activity at Report Time: RUWL TO SET CIBP

Start	End	Hrs	Activity Description
06:00	06:00	24.0	NU 10K FRAC TREE. PRESSURE TESTED TREE & CASING TO 6500 PSIG. HELD FOR 9 MIN & THEN DROPPED TO 5700 PSIG. SLOW LEAK OFF AFTER INTIAL DROP. SDFN.

06-27-2008 **Reported By** HISLOP

Daily Costs: Drilling	\$0	Completion	\$4,899	Daily Total	\$4,899
Cum Costs: Drilling	\$583,183	Completion	\$154,100	Well Total	\$737,283

MD 6,500 TVD 6,500 Progress 0 Days 10 MW 0.0 Visc 0.0
 Formation : PBTB : 6456.0 Perf : PKR Depth : 0.0

Activity at Report Time: TEST 4-1/2" CASING

Start	End	Hrs	Activity Description
06:00	06:00	24.0	MIRU CUTTERS WIRELINE. SET 10K CIBP @ 6360'. POH. RDWL. SDFN.

06-28-2008 Reported By JOE VIGIL

Daily Costs: Drilling	\$0	Completion	\$1,723	Daily Total	\$1,723
Cum Costs: Drilling	\$583,183	Completion	\$155,823	Well Total	\$739,006

MD 6,500 TVD 6,500 Progress 0 Days 11 MW 0.0 Visc 0.0
 Formation : PBTB : 6456.0 Perf : PKR Depth : 0.0

Activity at Report Time: PREP TO MIRUSU

Start	End	Hrs	Activity Description
06:00	06:00	24.0	PRESSURE TESTED FRAC TREE & CASING TO 6500 PSIG. LOST 1000 PSIG IN 15 MIN. @ 10 MIN OPENED SURFACE CASING CAUSING 4-1/2" TO DROP AN ADDITIONAL 200 PSI. BLEW WELL DOWN. WO SERVICE UNIT.

07-03-2008 Reported By BAUSCH

Daily Costs: Drilling	\$0	Completion	\$3,348	Daily Total	\$3,348
Cum Costs: Drilling	\$583,183	Completion	\$159,171	Well Total	\$742,354

MD 6,500 TVD 6,500 Progress 0 Days 12 MW 0.0 Visc 0.0
 Formation : PBTB : 6456.0 Perf : PKR Depth : 0.0

Activity at Report Time: MIRUSU. LOOK FOR LEAK.

Start	End	Hrs	Activity Description
14:00	18:00	4.0	MIRUSU. ND FRAC VALVES. NU BOP. SDFN.

07-04-2008 Reported By BAUSCH

Daily Costs: Drilling	\$0	Completion	\$8,277	Daily Total	\$8,277
Cum Costs: Drilling	\$583,183	Completion	\$167,448	Well Total	\$750,631

MD 6,500 TVD 6,500 Progress 0 Days 13 MW 0.0 Visc 0.0
 Formation : PBTB : 6360.0 Perf : PKR Depth : 0.0

Activity at Report Time: ISOLATE CSG LEAK

Start	End	Hrs	Activity Description
07:00	17:00	10.0	RIH W/TENSION PKR. ISOLATED CSG LEAK BETWEEN 5282' TO 5387'. PKR FAILED. RELEASED PKR & LANDED TBG @ 5292' KB. ND BOP. NU TREE. RDMOSU. SI.

TUBING DETAIL LENGTH

WEATHERFORD 4-1/2" 32A PKR 5.27' (NOT SET)

1 JT 2-3/8" 4.7# N-80 TBG 32.78'

XN NIPPLE 1.30'

162 JTS 2-3/8" 4.7# N-80 TBG 5238.57'

2-3/8" N-80 NIPPLE & COUPLING .60'

BELOW KB 13.00'

LANDED @ 5292.00' KB

07-12-2008 Reported By BAUSCH

DailyCosts: Drilling	\$0	Completion	\$7,810	Daily Total	\$7,810
Cum Costs: Drilling	\$583,183	Completion	\$175,258	Well Total	\$758,441
MD	6,500	TVD	6,500	Progress	0
				Days	14
				MW	0.0
				Visc	0.0
Formation :	PBTD : 6360.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: MIRUSU. FIND HOLE IN CSG.

Start	End	Hrs	Activity Description
07:00	18:30	11.5	MIRUSU. ND WH. NU BOPE. POH W TBG. LD PKR. PU HD PKR. RIH. SET PKR @ 5282'. TEST TBG AND CSG TO 4000 PSIG. PKR WOULD NOT HOLD. MOVE PKR DN HOLE 90'. STILL WOULDN'T HOLD. POH 600'. RETEST TOOLS. PKR STILL LEAKED. UNSET PKR. POH. LD TOOLS. SIFWE.

07-15-2008 **Reported By** BAUSCH

DailyCosts: Drilling	\$0	Completion	\$6,729	Daily Total	\$6,729
Cum Costs: Drilling	\$583,183	Completion	\$181,987	Well Total	\$765,170
MD	6,500	TVD	6,500	Progress	0
				Days	15
				MW	0.0
				Visc	0.0
Formation :	PBTD : 6360.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: ISOLATE CSG LEAK

Start	End	Hrs	Activity Description
07:00	18:00	11.0	RIH W/4-1/2" HD PKR TO 4313'. SET & TESTED PKR. RELEASED & RIH. ATTEMPTED TO ISOLATE LEAK BETWEEN 5184' & 5509'. UNABLE TO LOCATE HOLE AFTER 21 PKR SETTINGS. RIH TO CIBP @ 6360'. TESTED BP TO 4000 PSIG. POH TO 5930'. PRESSURED BELOW PKR & WOULDN'T HOLE. PREP TO POH TO CHANGE TOOLS. SDFN.

07-16-2008 **Reported By** BAUSCH

DailyCosts: Drilling	\$0	Completion	\$9,315	Daily Total	\$9,315
Cum Costs: Drilling	\$583,183	Completion	\$191,302	Well Total	\$774,485
MD	6,500	TVD	6,500	Progress	0
				Days	16
				MW	0.0
				Visc	0.0
Formation :	PBTD : 6360.0		Perf :	PKR Depth : 0.0	

Activity at Report Time: PREP FOR FRAC

Start	End	Hrs	Activity Description
07:00	15:00	8.0	POH TO 4993' & SET PKR. TESTED ANNULUS TO 4000 PSIG FOR 15 MIN. LOST 100 PSIG. TESTED BELOW PKR TO 4000 PSIG FOR 15 MIN. LOST 650 PSIG. RETEST ANNULUS TO 4000 PSIG FOR 15 MIN. LOST 40 PSIG. RELEASED PKR. POH. LD TBG. ND BOP. NU FRAC VALVES. RDMOSU. PREP FOR FRAC.

07-30-2008 **Reported By** HISLOP

DailyCosts: Drilling	\$0	Completion	\$375	Daily Total	\$375
Cum Costs: Drilling	\$583,183	Completion	\$191,677	Well Total	\$774,860
MD	6,500	TVD	6,500	Progress	0
				Days	11
				MW	0.0
				Visc	0.0
Formation : WASATCH	PBTD : 6456.0		Perf : 5974 - 6233	PKR Depth : 0.0	

Activity at Report Time: FRAC

Start	End	Hrs	Activity Description
06:00	06:00	24.0	RU CUTTERS WIRELINE & PERFORATE NORTH HORN/Ba FROM 5974'-75', 5988'-89', 6009'-10', 6026'-27', 6045'-46', 6054'-55', 6072'-73', 6096'-97', 6138'-39', 6166'-67', 6198'-99', 6232'-33' @ 3 SPF @ 120° PHASING. RDWL. SDFN.

07-31-2008 **Reported By** HISLOP

DailyCosts: Drilling	\$0	Completion	\$151,147	Daily Total	\$151,147
Cum Costs: Drilling	\$583,183	Completion	\$342,824	Well Total	\$926,007
MD	6,500	TVD	6,500	Progress	0
				Days	12
				MW	0.0
				Visc	0.0

Formation : WASATCH

PBSD : 6456.0

Perf : 5043' - 6233'

PKR Depth : 0.0

Activity at Report Time: PREP TO MIRUSU

Start	End	Hrs	Activity Description
06:00	06:00	24.0	SICP 100 PSIG. RU HALLIBURTON. FRAC DOWN CASING WITH 165 GAL GYPTRON T-106, 8029 GAL LINEAR W/1# & 1.5# 20/40 SAND, 34679 GAL DELTA 200 W/123388# 20/40 SAND @ 1-4 PPG. MTP 5285 PSIG. MTR 46.2 BPM. ATP 3666 PSIG. ATR 43.4 BPM. ISIP 2389 PSIG. RD HALLIBURTON.
			RUWL. SET CFP @ 5934'. PERFORATED Ba FROM 5603'-04', 5645'-46', 5694'-95', 5719'-20', 5742'-43', 5756'-57', 5760'-61', 5773'-74', 5843'-44', 5852'-53', 5886'-87', 5919'-20' @ 3 SPF & 120° PHASING. RDWL. RU HALLIBURTON. FRAC DOWN CASING WITH 7204 GAL LINEAR W/1# & 1.5# 20/40 SAND, 38272 GAL DELTA 200 W/123220# 20/40 SAND @ 1-4 PPG. MTP 4737 PSIG. MTR 43.6 BPM. ATP 3052 PSIG. ATR 38.7 BPM. ISIP 1774 PSIG. RD HALLIBURTON.
			RUWL. SET CFP @ 5550'. PERFORATED Ca FROM 5358'-59', 5375'-77', 5383'-85', 5412'-13', 5438'-40', 5457'-60', 5506'-07' @ 3 SPF & 120° PHASING. RDWL. RU HALLIBURTON. FRAC DOWN CASING WITH. 7460 GAL LINEAR W/1# & 1.5# 20/40 SAND, 28367 GAL DELTA 200 W/98715 # 20/40 SAND @ 1-4 PPG. MTP 3011 PSIG. MTR 42.3 BPM. ATP 2329 PSIG. ATR 39.5 BPM. ISIP 1557 PSIG. RD HALLIBURTON.
			RUWL. SET CFP @ 5340'. PERFORATED Ca FROM 5043'-44', 5064'-65', 5092'-93', 5106'-07', 5163'-64', 5200'-01', 5228'-29', 5245'-46', 5259'-60', 5280'-81', 5314'-16' @ 3 SPF & 120° PHASING. RDWL. RU HALLIBURTON. FRAC DOWN CASING WITH 7120 GAL LINEAR W/1# & 1.5# 20/40 SAND, 25173 GAL DELTA 200 W/94677# 20/40 SAND @ 1-4 PPG. MTP 6343 PSIG. MTR 46.5 BPM. ATP 3735 PSIG. ATR 38.4 BPM. ISIP 1726 PSIG RD HALLIBURTON.
			RUWL. SET 6K CBP AT 4942'. RDWL. SDFN.

08-01-2008		Reported By		HAL IVIE							
Daily Costs: Drilling		\$0		Completion		\$51,522		Daily Total		\$51,522	
Cum Costs: Drilling		\$583,183		Completion		\$394,346		Well Total		\$977,529	
MD	6,500	TVD	6,500	Progress	0	Days	13	MW	0.0	Visc	0.0
Formation : WASATCH		PBSD : 6456.0				Perf : 5043' - 6233'		PKR Depth : 0.0			

Activity at Report Time: FLOW TEST

Start	End	Hrs	Activity Description
06:00	18:00	12.0	MIRUSU ROYAL RIG # 1. ND FRAC TREE. NU BOP. RIH W/ BIT & PUMP OFF SUB TO 4942'. RU TO DRILL OUT PLUGS. CLEANED OUT & DRILLED OUT PLUGS @ 4942', 5340', 5550', 5934' RIH. CLEANED OUT TO PBSD @ 6415' LANDED TBG AT 5131' KB. ND BOPE. NU TREE. PUMPED OFF BIT & SUB. RDMOSU.
			FLOWED 13 HRS. 32/64" CHOKE. FTP 100 PSIG. CP 100 PSIG. 60 BFPH. RECOVERED 780 BLW. 3420 BLWTR.
			TUBING DETAIL LENGTH
			PUMP OFF SUB 1.00'
			1 JT 2-3/8 4.7# YB N-80 TBG 32.84'
			XN NIPPLE 1.10'
			156 JTS 2-3/8 4.7# YB N-80 TBG 5083.09'
			BELOW KB 13.00'
			LANDED @ 5131.03' KB

08-02-2008	Reported By	HAL IVIE								
Daily Costs: Drilling	\$0	Completion	\$2,525	Daily Total	\$2,525					

Cum Costs: Drilling	\$583,183	Completion	\$396,871	Well Total	\$980,054
MD	6,500	TVD	6,500	Progress	0
Days	14	MW	0.0	Visc	0.0
Formation : WASATCH	PBTD : 6456.0	Perf : 5043' - 6233'	PKR Depth : 0.0		

Activity at Report Time: FLOW TEST

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 24 HRS. 32/64 CHOKE. FTP- 500 PSIG, CP- 1200 PSIG. 46 BFPH. RECOVERED 1107 BBLS, 2317 BLWTR.

08-03-2008 Reported By HAL IVIE

Daily Costs: Drilling	\$0	Completion	\$2,525	Daily Total	\$2,525
Cum Costs: Drilling	\$583,183	Completion	\$399,396	Well Total	\$982,579
MD	6,500	TVD	6,500	Progress	0
Days	15	MW	0.0	Visc	0.0
Formation : WASATCH	PBTD : 6456.0	Perf : 5043' - 6233'	PKR Depth : 0.0		

Activity at Report Time: FLOW TEST

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 24 HRS. 32/64 CHOKE. FTP- 500 PSIG, CP- 1000 PSIG. 36 BFPH. RECOVERED 881 BBLS, 1432 BLWTR.

08-04-2008 Reported By HAL IVIE

Daily Costs: Drilling	\$0	Completion	\$2,525	Daily Total	\$2,525
Cum Costs: Drilling	\$583,183	Completion	\$401,921	Well Total	\$985,104
MD	6,500	TVD	6,500	Progress	0
Days	16	MW	0.0	Visc	0.0
Formation : WASATCH	PBTD : 6456.0	Perf : 5043' - 6233'	PKR Depth : 0.0		

Activity at Report Time: FLOW TEST

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 24 HRS. 32/64" CHOKE. FTP 450 PSIG. CP 900 PSIG. 26 BFPH. RECOVERED 652 BLW. 780 BLWTR.

08-05-2008 Reported By HAL IVIE

Daily Costs: Drilling	\$0	Completion	\$2,525	Daily Total	\$2,525
Cum Costs: Drilling	\$583,183	Completion	\$404,446	Well Total	\$987,629
MD	6,500	TVD	6,500	Progress	0
Days	17	MW	0.0	Visc	0.0
Formation : WASATCH	PBTD : 6456.0	Perf : 5043' - 6233'	PKR Depth : 0.0		

Activity at Report Time: FLOW TEST. SHUT WELL IN @ 6AM, 8-5-08. WAIT ON PROD FACILITIES.

Start	End	Hrs	Activity Description
06:00	06:00	24.0	FLOWED 24 HRS. 32/64 CHOKE. FTP-350 PSIG, CP- 800 PSIG. 17 BFPH. RECOVERED 410 BBLS, 370 BLWTR. SHUT WELL IN @ 6AM, 8-5-08. WO FACILITIES.

FINAL COMPLETION DATE: 8/4/08

08-27-2008 Reported By DUANE COOK

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0
Cum Costs: Drilling	\$583,183	Completion	\$404,446	Well Total	\$987,629
MD	6,500	TVD	6,500	Progress	0
Days	18	MW	0.0	Visc	0.0
Formation : WASATCH	PBTD : 6456.0	Perf : 5043' - 6233'	PKR Depth : 0.0		

Activity at Report Time: INITIAL PRODUCTION

Start	End	Hrs	Activity Description
-------	-----	-----	----------------------

06:00 06:00 24.0 INITIAL PRODUCTION- OPENING PRESSURE: TP 1750 PSIG & CP 1800 PSIG. TURNED WELL OVER TO QUESTAR SALES AT 12:30 HRS, 8/26/08. FLOWED 1987 MCFD RATE ON 14/64" CHOKE. STATIC 490. QGM METER #7843.

08-28-2008 Reported By ROGER DART

Daily Costs: Drilling \$0 Completion \$0 Daily Total \$0
 Cum Costs: Drilling \$583,183 Completion \$404,446 Well Total \$987,629
 MD 6,500 TVD 6,500 Progress 0 Days 19 MW 0.0 Visc 0.0
 Formation : WASATCH PBTD : 6456.0 Perf : 5043' - 6233' PKR Depth : 0.0
 Activity at Report Time: ON SALES

Start End Hrs Activity Description

06:00 06:00 24.0 FLOWED 822 MCF, 5 BC & 140 BW IN 24 HRS ON 14/64" CHOKE, TP 1225 PSIG, CP 1600 PSIG.

08-29-2008 Reported By ROGER DART

Daily Costs: Drilling \$0 Completion \$0 Daily Total \$0
 Cum Costs: Drilling \$583,183 Completion \$404,446 Well Total \$987,629
 MD 6,500 TVD 6,500 Progress 0 Days 20 MW 0.0 Visc 0.0
 Formation : WASATCH PBTD : 6456.0 Perf : 5043' - 6233' PKR Depth : 0.0
 Activity at Report Time: ON SALES

Start End Hrs Activity Description

06:00 06:00 24.0 FLOWED 742 MCF, 0 BC & 169 BW IN 24 HRS ON 14/64" CHOKE, TP 1225 PSIG, CP 1600 PSIG.

09-02-2008 Reported By ROGER DART

Daily Costs: Drilling \$0 Completion \$0 Daily Total \$0
 Cum Costs: Drilling \$583,183 Completion \$404,446 Well Total \$987,629
 MD 6,500 TVD 6,500 Progress 0 Days 21 MW 0.0 Visc 0.0
 Formation : WASATCH PBTD : 6456.0 Perf : 5043' - 6233' PKR Depth : 0.0
 Activity at Report Time: ON SALES

Start End Hrs Activity Description

06:00 06:00 24.0 08/30/08 - FLOWED 671 MCF, 1 BC & 195 BW IN 24 HRS ON 14/64" CHOKE, TP 1226 PSIG, CP 1600 PSIG.

08/31/08 - FLOWED 629 MCF, 3 BC & 140 BW IN 24 HRS ON 14/64" CHOKE, TP 1050 PSIG, CP 1400 PSIG.

09/01/08 - FLOWED 608 MCF, 0 BC & 155 BW IN 24 HRS ON 14/64" CHOKE, TP 1025 PSIG, CP 1400 PSIG.

09/02/08 - FLOWED 589 MCF, 5 BC & 150 BW IN 24 HRS ON 14/64" CHOKE, TP 1000 PSIG, CP 1400 PSIG.

Event No 2.0 Description

Operator EOG RESOURCES, INC WI % 100.0 NRI % 82.5

Reported By

Daily Costs: Drilling \$0 Completion \$0 Daily Total \$0
 Cum Costs: Drilling \$0 Completion \$0 Well Total \$0
 MD 0 TVD 0 Progress 0 Days 0 MW 0.0 Visc 0.0
 Formation : PBTD : 0.0 Perf : PKR Depth : 0.0
 Activity at Report Time:

Start	End	Hrs	Activity Description			
Event No	3.0		Description			
Operator	EOG RESOURCES, INC		WI %	100.0	NRI %	82.5

Reported By

Daily Costs: Drilling	\$0	Completion	\$0	Daily Total	\$0						
Cum Costs: Drilling	\$0	Completion	\$0	Well Total	\$0						
MD	0	TVD	0	Progress	0	Days	0	MW	0.0	Visc	0.0
Formation :		PBTD : 0.0		Perf :		PKR Depth : 0.0					
Activity at Report Time:											

Start	End	Hrs	Activity Description			
-------	-----	-----	----------------------	--	--	--

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-3355
2. NAME OF OPERATOR: EOG Resources, Inc.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Chapita Wells Unit
3. ADDRESS OF OPERATOR: 1060 East Highway 40 Vernal UT 84078	7. UNIT or CA AGREEMENT NAME: Chapita Wells Unit 722-32
PHONE NUMBER: (435) 789-0790	8. WELL NAME and NUMBER: 43-047-38862
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2071' FSL & 713' FEL 39.990914 LAT 109.343875 LON	9. API NUMBER: 43-047-38862
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 9S 23E S.L.B. & M.	10. FIELD AND POOL, OR WILDCAT: Natural Buttes/Wasatch

COUNTY: Uintah

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Site Facility Diagram
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Attached please find a site facility diagram.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

NAME (PLEASE PRINT) Mickenzie Thacker	TITLE Operations Clerk
SIGNATURE <i>Mickemie Thacker</i>	DATE 9/19/2008


(This space for State use only)

RECEIVED

Sept. 24 2008

DIV. OF OIL, GAS & MINING

Geogresources Site Facility Diagram



Well Name: CHAPITA WELLS UNIT 722-32
1/4 1/4: NE/SE **Sec:** 32 **T:** 9S **R:** 23E
County: Uintah **State:** UTAH
Lease: ML-3355
UNIT\PA#: 892000905ABCDEFGHIJKLNP

Site facility diagrams & site security plans are located at the Vernal office in Vernal, Utah. The office is located at 1060 East Hwy 40 and normal business hours are 7:00 a.m. to 4:30 p.m. Mon -Thurs and 7:00 a.m. to 1:00 p.m. Fridays.

Valve	Production Phase	Sales Phase	Water Drain
PV	O	SC	SC
LV	SC	O	SC
WD	SC	SC	O

DATED 9/19/2008

Abbreviations

AM= Allocation Meter
 AR = Access Road
 CHT = Chemical Tank
 COMP = Compressor
 CON = Condensor
 CT = Condensate Tank
 DL = Dump Line
 EP = Electrical Panel
 ET = Emergency Tank
 FW = Firewall
 LACT = LACT Unit
 LH = Line Heater
 LV = Load Valve
 MAN = Manifold
 MB = Methanol Bath
 O = Open
 PL = Production Line
 PP = Power Pole
 PT = Propane Tank
 PU = Pumping Unit
 PV = Production Valve
 PW = Produced Water
 RL = Recycle Line
 RP = Recycle Pump
 RV = Recycle Valve
 SC = Sealed Closed
 SGS = Sales Gas Scrubber
 SL = Sales Line
 SM = Sales Meter
 SO = Sealed Open
 SP = Separator
 SV = Sales Valve
 T = Treater
 TP = Trace Pump
 WD = Water Drain
 WDP = Water Disposal Pump
 WFP = Water Flood Pump
 WH = Wellhead


----- = Buried Line
 _____ = Unburied Line

△ = Meter Display

□ = Meter Tube

○ = Production Valve

× = Valve



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input checked="" type="checkbox"/>	DRY <input type="checkbox"/>	OTHER <input type="checkbox"/>	7. UNIT or CA AGREEMENT NAME	
b. TYPE OF WORK:		NEW WELL <input checked="" type="checkbox"/>	HORIZ. LATS. <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	RE-ENTRY <input type="checkbox"/>	DIFF. RESVR. <input type="checkbox"/>	OTHER <input type="checkbox"/>
2. NAME OF OPERATOR:						43-047-38862	
3. ADDRESS OF OPERATOR:						10 FIELD AND POOL, OR WILDCAT	
600 17th St., Suite 1000N CITY Denver STATE CO ZIP 80202						Natural Buttes/Wasatch	
4. LOCATION OF WELL (FOOTAGES)						11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:	
AT SURFACE: 2071' FSL & 713' FEL 39.990914 LAT 109.343875 LON						NESE 32 9S 23E S	
AT TOP PRODUCING INTERVAL REPORTED BELOW: Same						12. COUNTY	
AT TOTAL DEPTH: Same						Utah	
13. STATE						UTAH	

14. DATE SPUNDED:	15. DATE T.D. REACHED:	16. DATE COMPLETED:	ABANDONED <input type="checkbox"/>	READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL):
5/12/2008	6/11/2008	8/26/2008			5202' NAT GL
18. TOTAL DEPTH: MD 6,500	19. PLUG BACK T.D.: MD 6,456	20. IF MULTIPLE COMPLETIONS, HOW MANY? *	21. DEPTH BRIDGE MD		
TVD	TVD		PLUG SET: TVD		
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)			23.		
RST/CBL/CCL/VDL/GR Temp			WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis)		
			WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report)		
			DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)		

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
12-1/4	9-5/8 J-55	36.0	0	2,221		1250			
7-7/8	4-1/2 N-80	11.6	0	6,498		1030			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-3/8	5,131							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) Wasatch	5,043	6,233			5,974 6,233		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(B)					5,603 5,920		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)					5,358 5,507		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)					5,043 5,316		3	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
5974-6233	42,873 GALS GELLED WATER & 123,388# 20/40 SAND
5603-5920	45,476 GALS GELLED WATER & 123,220# 20/40 SAND
5358-5507	35,827 GALS GELLED WATER & 98,715# 20/40 SAND

29. ENCLOSED ATTACHMENTS:

- ☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: _____

30. WELL STATUS:

Producing

RECEIVED

SEP 30 2008

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 8/26/2008		TEST DATE: 9/2/2008		HOURS TESTED: 24		TEST PRODUCTION RATES: →	OIL – BBL: 5	GAS – MCF: 589	WATER – BBL: 150	PROD. METHOD: Flows
CHOKE SIZE: 14/64"	TBG. PRESS. 1,000	CSG. PRESS. 1,400	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL: 5	GAS – MCF: 589	WATER – BBL: 150	INTERVAL STATUS: Producing

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

Sold

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
Wasatch	5,043	6,233		Green River Mahogany Uteland Butte Wasatch Chapita Wells Buck Canyon Price River	1,428 2,032 4,178 4,282 4,838 5,530 6,340

35. ADDITIONAL REMARKS (Include plugging procedure)


See attached page for additional information.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Mary A. Maestas

TITLE Regulatory Assistant

SIGNATURE



DATE 9/26/2008

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

Chapita Wells Unit 722-32 – ADDITIONAL REMARKS (CONTINUED):

28. ACID, FRACTURE TREATMENT, CEMENT SQUEEZE, ETC.

5043-5316	32,293 GALS GELLED WATER & 94,677# 20/40 SAND
-----------	-----------------------------------------------

Perforated the North Horn/Ba from 5974-75', 5988-89', 6009-10', 6026-27', 6045-46', 6054-55', 6072-73', 6096-97', 6138-39', 6166-67', 6198-99', 6232-33' w/ 3 spf.

Perforated the Ba from 5603-04', 5645-46', 5694-95', 5719-20', 5742-43', 5756-57', 5760-61', 5773-74', 5843-44', 5852-53', 5886-87', 5919-20' w/ 3 spf.

Perforated the Ca from 5358-59', 5375-77', 5383-85', 5412-13', 5438-40', 5457-60', 5506-07' w/ 3 spf.

Perforated the Ca from 5043-44', 5064-65', 5092-93', 5106-07', 5163-64', 5200-01', 5228-29', 5245-46', 5259-60', 5280-81', 5314-16' w/ 3 spf.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 7

REPORT OF WATER ENCOUNTERED DURING DRILLING

Well name and number: CWU 722-32

API number: 4304738862

Well Location: QQ NESE Section 32 Township 9S Range 23E County UINTAH

Well operator: EOG

Address: 1060 E HWY 40

city VERNAL state UT zip 84078

Phone: (435) 781-9111

Drilling contractor: ASPEN DRILLING

Address: 560 S. COMMERCIAL DR. UNIT #1

city GRAND JUNCTION state CO zip 81505

Phone: (970) 242-9592

Water encountered (attach additional pages as needed):

DEPTH		VOLUME (FLOW RATE OR HEAD)	QUALITY (FRESH OR SALTY)
FROM	TO		
		NO WATER	DRILLED WITH FULID

Formation tops: 1 _____ 2 _____ 3 _____
(Top to Bottom) 4 _____ 5 _____ 6 _____
 7 _____ 8 _____ 9 _____
 10 _____ 11 _____ 12 _____

If an analysis has been made of the water encountered, please attach a copy of the report to this form.

I hereby certify that this report is true and complete to the best of my knowledge.

NAME (PLEASE PRINT) Mary A. Maestas

TITLE Regulatory Assistant

SIGNATURE Mary A. Maestas

DATE 9/26/2008



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
<http://www.blm.gov/ut/st/en.html>



IN REPLY REFER TO
3180
UT-922

July 7, 2009

Debbie Spears
EOG Resources, Inc.
600 17th Street, Suite 1000N
Denver, Colorado 80202

Re: Consolidated Wasatch Formation PA "H, J"
Chapita Wells Unit
Uintah County, Utah

Dear Ms. Spears:

The Consolidated Wasatch Formation PA "H, J", Chapita Wells Unit, CRS No. UTU63013BK, AFS No. 892000905BK, is hereby approved effective as of August 1, 2008, pursuant to Section 11 of the Chapita Wells Unit Agreement, Uintah County, Utah.

The Consolidated Wasatch Formation PA "H, J" results in an initial consolidated participating area of 640.00 acres and is based upon the completion of the following wells as capable of producing unitized substances in paying quantities.

To: 15871

WELL NO.	API NO.	LOCATION	LEASE NO.
CWU 722-32	43-047-38862	NE $\frac{1}{4}$ SE $\frac{1}{4}$, 32-9S-23E	STATE
CWU 732-32	43-047-39599	NE $\frac{1}{4}$ SW $\frac{1}{4}$, 32-9S-23E	STATE

from
16862
16899

Copies of the approved request are being distributed to the appropriate agencies and one copy is returned herewith. Please advise all interested parties of the approval of the Consolidated Wasatch Formation PA "H, J", Chapita Wells Unit, and the effective date.

ALSO: from 16555
*4304739199 CWU 699-32 **
*4304739216 CWU 698-32 **
**ALSO IN sec 32 9S 23E*

RECEIVED

JUL 13 2009

Enclosure

DIV. OF OIL, GAS & MINING

Sincerely,

/s/ Becky J. Hammond

Becky J. Hammond
Chief, Branch of Fluid Minerals

Also from 16555
**4304737494 CWU 689-32*
**4304739056 CWU 719-32*

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: EOG Resources, Inc. Operator Account Number: N 9550
Address: 1060 East Highway 40
city Vernal
state UT zip 84078 Phone Number: (435) 781-9145

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-38067	CHAPITA WELLS UNIT 1238-22		SWNE	22	9S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	16961	13650	6/16/2008			7/1/2008	
Comments: MESAVERDE — 7/30/09							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-38608	CHAPITA WELLS UNIT 1096-22		SWSE	22	9S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	16935	13650	6/21/2008			8/1/2008	
Comments: MESAVERDE — 7/30/09							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-047-38862	CHAPITA WELLS UNIT 722-32		NESE	32	9S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	16862	15871	5/12/2008			8/1/2008	
Comments: WASATCH — 7/30/09							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Mickenzie Thacker

Name (Please Print)

Mickenzie Thacker

Signature

Operations Clerk

7/30/2009

Title

Date

RECEIVED

JUL 30 2009

DIV. OF OIL, GAS & MINING



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
<http://www.blm.gov/ut/st/en.html>



IN REPLY REFER TO
3180
UT-922

July 24, 2009

Debbie Spears
EOG Resources, Inc.
600 17th Street, Suite 1000N
Denver, Colorado 80202

Re: Initial Consolidated Wasatch
Formation PA "A-H, J"
Chapita Wells Unit
Uintah County, Utah

Dear Ms. Spears:

The Initial Consolidated Wasatch Formation PA "A-H, J", Chapita Wells Unit, CRS No. UTU63013BM, AFS No. 892000905BM, is hereby approved effective as of September 1, 2008, pursuant to Section 11 of the Chapita Wells Unit Agreement, Uintah County, Utah.

The Initial Consolidated Wasatch Formation PA "A-H, J" results in an initial consolidated participating area of 15,904.22 acres and is based upon the completion of the following wells as capable of producing unitized substances in paying quantities.

to 4905

WELL NO.	API NO.	LOCATION	LEASE NO.
CWU 731-32	43-047-39582	NE $\frac{1}{4}$ NW $\frac{1}{4}$, 32-9S-23E	STATE
CWU 717-7	43-047-39055	SE $\frac{1}{4}$ SW $\frac{1}{4}$, 7-9S-23E	UTU0343
CWU 1229-7	43-047-38113	NE $\frac{1}{4}$ NE $\frac{1}{4}$, 7-9S-23E	UTU0343

from
16896
16948
16934

Copies of the approved request are being distributed to the appropriate agencies and one copy is returned herewith. Please advise all interested parties of the approval of the Initial Consolidated Wasatch Formation PA "A-H J", Chapita Wells Unit, and the effective date.

also entity 15871 to 4905

API	WELL NAME	QTR/QTR	SEC	TWP	RNG
✓ 4304737415	CWU 695-32	SWNE	32	0908	230E
✓ 4304737424	CWU 689-33	NESW	33	0908	230E
✓ 4304738862	CWU 722-32	NESE	32	0908	230E
4304739056	CWU 719-33	SWSW	33	0908	230E
4304739197	CWU 697-32	SWNW	32	0908	230E
4304739199	CWU 699-32	SWSW	32	0908	230E
✓ 4304739216	CWU 698-32	SWSE	32	0908	230E
✓ 4304739599	CWU 732-32	NESW	32	0908	230E

Sincerely,

/s/ Terry Catlin

Terry Catlin
Acting Chief, Branch of Fluid Minerals

RECEIVED

JUL 29 2009

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: EOG Resources, Inc.
Address: 1060 East Highway 40
city Vernal
state UT zip 84078

Operator Account Number: N 9550

Phone Number: (435) 781-9145

Well 1

API Number	Well Name	QQ	Sec	Twp	Rng	County
43-047-38862	CHAPITA WELLS UNIT 722-32	NESE	32	9S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
C	15871	4905	5/12/2008	9/1/2008		
Comments: WASATCH — 8/24/09						

Well 2

API Number	Well Name	QQ	Sec	Twp	Rng	County
43-047-39599	CHAPITA WELLS UNIT 732-32	NESW	32	9S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
C	15871	4905	6/5/2008	9/1/2008		
Comments: WASATCH — 8/24/09						

Well 3

API Number	Well Name	QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
Comments:						

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Mickenzie Thacker

Name (Please Print)

Mickenzie Thacker

Signature

Operations Clerk

8/20/2009

Title

Date

RECEIVED

AUG 19 2009

DIV. OF OIL, GAS & MINING